

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 4 p9.55

For corners in

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 2E	B - 1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
 OSCODA COUNTY  
 FILED

2 AUG 95 9:33 A.M.

PATSY J. PETERS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on June 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO-1924 Guy Veal  
 Mon-Set 36"x1" Iron Post  
 WIT: 7" J.Pine S45 $\frac{1}{2}$  $^{\circ}$ E 66 lks.  
 6" J.Pine S33 $\frac{1}{2}$  $^{\circ}$ W 69 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Monument - Found GLO Monument (pipe & cap), this position not established by original survey the monument is accepted as a careful and faithful establishment of the position of the corner.

SURVEY &  
 REMONUMENTATION

NOV 21 1995

COMMISSION


**APPROVED**

County Remonumentation  
 Peer Review Group

NCC/31/206 95  
 JULY

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon-US GLO pipe & cap  
 WIT: Fd. nail Wit sign (note: a small nail 1 $\frac{1}{2}$ " above a dock spike checks the distance record on sign. Our measured distance is to the head of the dock spike.) S45 $^{\circ}$ W 64.20'  
 Fd. dock spike E. face 10" B.Oak S12 $^{\circ}$ E 39.55'  
 Centerline E-W trail road North 23' $\pm$   
 Fd. dock spike W. face 8" J.Pine N22 $^{\circ}$ E 59.95'  
 Set pole barn nail W. face 5" J.Pine N10 $^{\circ}$ W 4.14'



Signed by Marvin E. Myers

Date July 29, 1995

Surveyor's Michigan License No. 31600