

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 99.54

For corners in Oscoda <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 25N R 2E	C - 1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED
 2 AUG 95 9:33 A.M.
 PATSY J. PETERS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO-1924 Guy Veal L.2 pg.24 N. Caldwell Nov. 1963
 Mon-Set 36"x2" Iron Post with Brass Cap Mon-Fd. US GLO pipe & cap
 WIT: 10" Norway N18°E 103 lks. WIT: 14" J.Pine SE 33.90'
 12" Norway N25½°W 165 lks. GLO July 1839 William Coon
 Local cor. 1½" Iron Pipe Mon-Post
 N41°E 10 lks. set by Seely 1915 Wit- 4" Spruce Pine N18°E 17 lks
 Along side wood Post set by Randall 1884 5" Spruce Pine N14°W 34 lks

N. Caldwell Apr. 1964
 Mon-Fd. GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found US GLO Monument. Accepted as a careful and faithful establishment of the position of the corner.

SURVEY &
 REMONUMENTATION
 NOV 2 1995
 COMMISSION

APPROVED
 County Remonumentation
 Peer Review Group

NCC/31406 95
 JULY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-US GLO pipe & cap
 WIT: US GLO Mon. Sec. 31 & 32, T26N, R2E S83°E 33.00'
 Fd. 21" Norway with USFS location sign North 97.50'
 Fd. nail E. side USFS locator post N04°E 43.00'
 Fd. cabin spike in NE face 6" J.Pine N16°W 50.63'
 Fd. nail E. side USFS location post N46°E 53.53'
 Fd. nail N. side utility pole S87°W 42.59'



Signed by Marvin E. Myers
 31600
 Surveyor's Michigan License No. _____

Date July 29, 1995