

NOV 4 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda (County) Located In: 26N 1E Corner Code # M-1

1. Public Land Survey	T	<u>26N</u>	R	<u>2E</u>	<u>M-1</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Liber 4 pg. 57

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

2 AUG 95 9:34 A.M.

PATSY J. PETERS  
Register of Deeds Stamp & File Number  
REGISTER OF DEEDS

I, Marvin E. Myers, in a field survey on May 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-L. Clason May 1839  
Mon-Post  
WIT: 16" Y.Pine  
12" Spruce  
Swamp South 2.6 chs.
- Fargo Engineering 1908-1909  
Mon-Fd. stake  
WIT: 12" Spruce N68½°E 16 lks.  
8" Spruce N16½°W 26 lks.
- G.F. Delamatter Feb. 25, 1924  
Mon-Fd. post  
WIT: 30" W.Pine S04°E 13½ lks.  
6" Fir S27°W 36 lks.  
12" S.Pine N68°E 16 lks.  
8" S.Pine N66°W 26 lks.
- GLO-G. Veal Oct. 1935  
Mon-Fd. 1" pipe set by Fargo  
Replaced pipe with Conc.  
Mon. & Brass Cap  
WIT: 7" J.Pine N37°E 85½ lks.  
8" J.Pine N86°W 52½ lks.
- G.D. Henning May 7, 1941  
Mon-US GLO  
WIT: None given
- L. pg.222 L.G. Beauregard April 18, 1979  
Mon-Set ½"x24" Bar & Cap from GLO witness  
dependent re-survey 1935  
WIT: 12" J.Pine N37°E 56.43'  
8" J.Pine N86°W 34.65'  
8" J.Pine N65°W 17.40'
- L.3, pg.425 Ed. J. McCombs May 10, 1984  
Mon-Fd. Rebar & Cap  
WIT: dead Spruce N55°W 12.53'  
dead Spruce N80°W 35.00'  
Pine N40°E 56.80'  
10" Pine S54°E 52.79'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" Bar & Cap in North track of trail road  
Found still stand US GLO 8" J.Pine (with scribing on face) N80°W 34.65'  
Found 15" J.Pine  
And is accepted as a perpetuation of the original government corner.

APPROVED

County Remonumentation  
Peer Review Group

NCC/31/406 95  
JULY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Set 5/8" X 30" Bar with Standard County Cap  
WIT: Set nail SW face 8" J.Pine N54°W 22.06'  
Fd. 15" J.Pine N93°E (recorded as N87°E) 56.43'  
Set nail SE face 15" B.Oak N35°E 76.58'  
Set nail side Red Top USFS location post East 33.21'



Signed by Marvin E. Myers

Date July 29, 1995

Surveyor's Michigan License No. 31600