

NOV 8 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 pg. 58

For corners in Oscoda (County) Located In: Corner Code #

1. Public Land Survey T 26N R 2E M-3

2. Property Controlling in Section S T R

3. Miscellaneous Property in Section S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
OSCODA COUNTY
FILED
2 AUG 95 9:34 A.M.
PATSY J. PETERS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on May 19, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-L. Clason May 1839 Mon-Post WIT: 12" Y.Pine N60°W 6.66 chs. 4" Spruce S62°E 4.87 chs. 6" Spruce N51°E 5.21 chs.
- Fargo Engineering 1908-1909 Mon-Unknown WIT: None given
- C.O. Seeley May 29, 1912 Mon-Post WIT: None given
- GLO-G. Veal Oct. 1935 Mon-Fd. 4"x4" Post perpetuate original by J. Randall 1887 Set Conc. Mon. with Brass Tablet at point WIT: 8" J.Pine S87½°W 67½ lks. 9" J.Pine S87½°W 125 lks.
- G. Henning May 1941 Mon-US GLO Mon.
- G.D. Henning 1953 Mon-US GLO Mon.
- G.A. Shadko 1958 Mon-US GLO Mon. WIT: None given
- Consumers Power Co. Oct. 1979 Mon-US GLO Mon WIT: Cor. fence post West 1.0' 14" J.Pine ENE 94.28' 8" J.Pine NNE 57.64'
- L.3, pg.425 Edwin J. McCombs May 10, 1984 Mon-Fd. Gov't Mon. WIT: 1.00' NW of cor. fence post 14" J.Pine ENE 44.28' 8" J.Pine NNE 57.64'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found US GLO concrete monument with brass tablet.
Corner fence post with USFS location poster S50°E 1.00'
And is accepted as a perpetuation of the original government corner.

APPROVED

County Remonumentation
Peer Review Group

NCC/31/AUG 95
JULY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-US GLO Mon.
- WIT: Nail in E. face 7" J.Pine S15°W 44.05'
- Nail in N. face 9" J.Pine S70°E 52.28'
- Nail in E. face 5" J.Pine N05°E 20.64'
- Nail in S. face 3" J.Pine S75°W 10.37'
- Centerline N-S road East 18.60'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600