

REVISION

NOV 1 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda  
(County)

Located In: 26N 1E

Corner Code # 1

Liber 4 pg. 59

- 1. Public Land Survey T 26N R 1E
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED  
2 AUG 95 9:35 A.M.  
PATSY J. PETERS  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on May 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-L. Clawon May 1839 Mon-Post WIT: 5" Spruce S45 $\frac{1}{2}$ °W 17 lks. 5" Spruce N20 $\frac{1}{2}$ °W 24 lks.
- GLO-G. Veal Oct. 1935 Mon-No evidence set Conc. Mon. wit 3 $\frac{1}{2}$ " Brass Tablet WIT: 9" J.Pine N88°E 19 $\frac{1}{2}$  lks. 5" J.Pine N25 $\frac{1}{2}$ °W 26 $\frac{1}{2}$  lks. Set by propertate distance
- G.D. Henning 1953 Mon-US GLO Conc. Mon. WIT: None given
- G.A. Shadko 1958 Mon-US GLO Mon. WIT: None given
- L. 3, pg.88 F. King April 1986 Mon-Fd. Std. Co. corner N-S Rd. WIT: Red top post East 33.00' 8" J.Pine S40°W 42.65'  $\frac{1}{2}$ " Iron West 33.06' 12" J.Pine N63°W 19.80'
- L.3, pg.31 F.King Mon-Fd. Std. Co. corner N-S Rd. WIT: Red top post East 33.00' 8" J.Pine S40°W 42.65'  $\frac{1}{2}$ " Iron West 33.06' 12" J.Pine N63°W 19.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found standard Oscoda County Monument in centerline North - South Road and accepted as the best available evidence of the position of the Original corner.

**APPROVED**

County Remonumentation  
Peer Review Group

*NCC/31 AUG 95  
JULY*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Std. Oscoda County Mon. in centerline N-S Rd.
- WIT: Fd. USFS locate post S85°E 33.00'
- Fd.  $\frac{1}{2}$ " bar N85°W 33.06'
- Fd. spike in S. face 12" J.Pine N63°W 19.80'
- Fd. spike in W. face 8" J.Pine S40°W 42.65'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600