

NOV 11 1995  
 OSCODA

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 pg. 6

For corners in Oscoda (County) Located In: 26N R 2E Corner Code # AA-6

1. Public Land Survey T 26N R 2E  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 OSCODA COUNTY  
 FILED  
 2 AUG 95 9:35 A.M.  
 PATSY J. PETERS  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on May 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	15	14	13						
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-L. Clawson 1839  
 Mon-Post  
 WIT: 8" Aspen S62°W 44 lks.  
 7" Aspen N85°W 24 lks.
- Randall Feb. 1893  
 Mon-Unknown  
 WIT: None given
- C.O. Seeley Sept. 21, 1914  
 Mon-Set Post  
 WIT: NBT 12" Soft Maple S66°E 0.39 lks.  
 NBT 10" Water Elm S21°W 1.08 3/4 lks.
- GLO-G. Veal Oct. 1935  
 Mon-Set Conc. Mon. with  
 Brass Tablet by proportionate distance  
 WIT: 4" Birch S56°E 19 lks.  
 4" Elm N83½°W 62½ lks.  
 Fence N. 12 lks. & E. 2 lks.
- G. Henning 1953  
 Mon-Fd. US GLO Mon.  
 WIT: NBT Spike 10" J.Pine N40½°E 47.00'  
 NBT Spike 7" J.Pine S21°W 51.20'
- G. Henning Aug. 1956  
 Mon-Broken off  
 WIT: US 6" Birch S56°E 12.50'  
 BT 16" Maple S29°W 52.50'  
 BT 8" Maple N47°E 44.80'

- L.2, pg.170 N. Caldwell July 28, 1  
 Mon-Unknown  
 WIT: ½" Bar & Cap N88 3/4"E 33.00'
- LCRC L.3, pg.90
- L.4, pg.489 N. Caldwell July 16, 1  
 Mon-Fd. 6" Dia. Conc. Mon. replace  
 with USFS 5"x5"x36" Conc. Mon.  
 WIT: ½" Rerod N87°W 33.00'  
 ½" Rerod & Cap #12018 N89°E  
 33.20'  
 Power Pole N24°W 69.25'  
 8" Maple S35°E 25.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found USFS 5"x5" Concrete Monument. Accepted as a careful and faithful establishment of the position of the corner.

**APPROVED**

County Remonumentation  
 Peer Review Group

*NCC/31/706 95  
 JULY*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-USFS 5"x5" Conc. Mon.  
 WIT: ½" Rerod N87°W 33.00'  
 ½" Rerod & Cap #12018 N89°E 33.20'  
 Power Pole N24°W 69.25'  
 8" Maple S35°E 25.85'



Signed by Marvin E. Myers  
 Surveyor's Michigan License No. 31600

Date July 28, 1995