

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Oscoda (County)

Located In:

Corner Code #

*Liber 4 pg. 62*

26N 1E

M-7

- |                                       |   |            |   |           |       |       |
|---------------------------------------|---|------------|---|-----------|-------|-------|
| 1. Public Land Survey                 | T | <u>26N</u> | R | <u>2E</u> | _____ |       |
|                                       | T | _____      | R | _____     | _____ |       |
|                                       | T | _____      | R | _____     | _____ |       |
|                                       | T | _____      | R | _____     | _____ |       |
| 2. Property Controlling in Section    | S | _____      | T | _____     | R     | _____ |
|                                       | S | _____      | T | _____     | R     | _____ |
| 3. Miscellaneous Property in Section  | S | _____      | T | _____     | R     | _____ |
|                                       | S | _____      | T | _____     | R     | _____ |
| 4. Lot No. _____, Recorded Plat _____ |   |            |   |           |       |       |
| 5. Private Claims _____               |   |            |   |           |       |       |

STATE OF MICHIGAN  
 OSCODA COUNTY  
 FILED  
 2 AUG 95 9:35 A.M.  
 PATSY J. PETERS  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |   |  |
|--|---|--|
| GLO-L. Clawson May 1839<br>Mon-Post<br>WIT: 12" Aspen S85°W 4 lks.<br>12" Aspen N50°W 35 lks.<br>10" Aspen N78½°E 24 lks.<br>12" Aspen S75°E 26 lks. | C.O. Seeley Sept. 21, 1914<br>Mon-Fd. stake by Randall<br>(iron bar at stake)<br>WIT: NBT Balsam N19°W 1.10 chs.<br>Stone 2' dia. S26½°E 40 lks.                        | L.2, pg.114 N. Caldwell April 23, 1969<br>Mon-Fd. US GLO Mon. in C E-W & N roads<br>WIT: Guy Pole S68°W 93.40'<br>18" W.Pine N37°W 49.90'<br>Power Pole N68°W 83.40'                 |
| John Randall Dec. 28, 1887<br>Mon-Remark Post Fd. both USBT'S<br>WIT: 4" Fir N19°W 1.10 chs.   | GLO-G. Veal Oct. 1935<br>Mon-Fd. Iron Bar-Set by Randall 1887 from both original BT'S set at that point Conc. Mon. with Brass Tablet<br>WIT: 16" Balsam N19°W 109½ lks. | L.2, pg. 428 N. Caldwell July 26, 1977<br>Mon-Fd. US GLO Mon.<br>WIT: ½" Bar & Cap S45°E 46.00'<br>18" W.Pine N30°W 49.10'<br>½" Pipe N45°W 46.60'<br>S. edge of E-W road South 8.0' |
| C.O. Seeley May 29, 1912<br>Mon-Unknown<br>WIT: None given   | MSHD MKW 1958<br>Mon-Conc. Mon. ½" Iron<br>WIT: Guy Pole S68°W 93.37'<br>Power Pole N68°W 83.41'<br>18" W.Pine N37°W 49.85'   |  |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found ½" Bar in Monument Box. Replaced ½" x 16" bar and cap with 5/8" x 30" bar and standard Oscoda County cap. And is accepted as a perpetuation of the original government corner.

**APPROVED**

County Remonumentation  
Peer Review Group

*NCC/31/456 95  
JULY*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Mon-5/8" Bar with Standard Oscoda County cap in pavement box  
 WIT: Centerline E-W road North 5.50'±  
 Centerline road North is East 3.50'±  
 Nail & Tag SW side utility pole N60°W 83.41'  
 Nail 25" W.Pine N39°W 49.85'  
 Nail & Tag Guy Pole S75°W 93.37'  
 5½" W.Pine N47°E 77.45'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600