

1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Oscoda  
(County)

Located In: 26N R 2E

Corner Code # 8

1. Public Land Survey	T	<u>26N</u>	R	<u>2E</u>	<u>8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Liber 4 pg 63

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

2 AUG 95 9:36 A.M.

PATSY J. PETERS  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on June 4, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-L. Clawson May 1839  
Mon-Post  
WIT: 14" Maple S39½°W 38 lks.  
24" Maple N70°W 8 lks.

John Randall Dec. 27, 1887  
Mon-Set Post  
WIT: 7" Sugar S35°W 97 lks.  
20" Sugar N88°E 76 lks.

GLO- G. Veal Oct. 1935  
Mon-Accepted intersection of fences & G road extended Set Conc. Mon. with Brass Tablet  
WIT: 8" ELM S88°E 51 lks.  
13" Maple N72°W 73 lks.

MSHD N. Caldwell 1958  
Mon-GLO Mon. & Brass Tablet  
WIT: 22" Elm N88°W 152.25'  
20" Elm N30°W 123.05'  
8" Tri. Ash S66°E 93.00'

L.I, pg.116 N. Caldwell Sept. 25, 1971  
Mon-Unknown  
WIT: None given

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Oscoda County Standard Monument 24.7'± West of centerline M-72 in shoulder of road. Accepted as a careful and faithful establishment of the position of the corner.

APPROVED

County Remonumentation  
Peer Review Group

*NCC/31/28/95*  
*JULY*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Oscoda County Std. Mon.  
WIT: Fd. USFS location marker post; placed nail in N. face N81°W 55.62'  
Top center Conc. R/W marker post N37°W 52.47'  
South end Conc. culvert N30°E 91.55'  
Nail S. face 5" W.Pine S50°E 78.10'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600