

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 pg. 65

For corners in
Oscoda
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>26N</u>	R	<u>2E</u>	<u>10</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

2 AUG 95 9:36 A.M.

PATSY J. PETERS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Marvin E. Myers, in a field survey on June 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-L. Clawson May 1839
 Mon-Post
 WIT: 7" Spruce S51°W 22 lks.
 5" Spruce N68½°W 10 lks.

GLO-G. Veal Oct. 1935
 Mon-Fd. 4"x4"x24" Wood Post
 at fence intersection set
 at this point Conc. Mon.
 with Brass Tablet
 WIT: 6" J.Pine N50°E 71 lks.
 8" J.Pine S25 3/4°W 67 lks.
 E-W road North 1.00 chs.

LCRC L.3, pg.258
 Gary Wilson Sept. 21, 1992
 Mon-Fd. GLO Mon.
 80' South of E-W Co. Rd. &
 29' W. of Sand Trail
 WIT: 10" B.Oak N18°E 134.73'
 ½" Bar & Cap S70°E 135.00'
 10" B.Oak N02°W 136.65'

Randall Sept. 1, 1883
 Remarkd post fd. original & verified
 by measurement to BT down & decaying
 WIT: 5" Spruce N68½°W 10 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found US GLO Monument and accepted as a perpetuation of the original Government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-US GLO Conc. Mon. with iron along side
 WIT: 80'± South of E-W road
 29'± West of Sand Trail Road
 Fd. ½" Bar & Cap 25881 West 60.00'
 Fd. ½" Bar & Cap 25881 S70°E 135.00'
 Fd. 10" B.Oak N18°E 134.73'
 Fd. 10" B.Oak N02°W 136.65'
 USFS Survey Lat 44°36'57".34856
 Long 84°15'03".39669

APPROVED

County Remonumentation
 Peer Review Group

*NCC/31/206 95
 JULY*



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600