

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Oscoda
 (County)

Located In: Section 16

Corner Code #
16

Liber 4 pg. 66

- | | | | | | |
|------------------------------------|---|-----|---|----|-----------|
| 1. Public Land Survey | T | 26N | R | 2E | <u>16</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous | S | | T | R | |
| Property in Section | S | | T | R | |

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED
 2 AUG 95 9:36 A.M.
 PATSY J. PETERS
 Register of Deeds

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	6	5	4	3	2	1				
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Marvin E. Myers, in a field survey on June 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-L. Clawson May 1839
 Mon-Post
 WIT: 8" Spruce S60½°W 9 lks.
 7" Spruce N65 3/4°W 12 lks.
 6" Spruce N80½°E 10 lks.
 4" Spruce S48°E 4 lks.

GLO-G. Veal 1935
 Mon-Accepted fence intersection as best available evidence
 Set.Conc. Mon. with Brass Tablet
 WIT: 7" J.Pine N82½°E 35½ lks.
 8" J.Pine S02½°W 34 lks.
 8" J.Pine S46½°W 31½ lks.
 8" J.Pine N70½°W 56½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found US GLO Monument and burnt stumps of all USGLO 1935 accessories. Accepted as the best available evidence of the RE-Establishment of the Original corner.

APPROVED

County Remonumentation
 Peer Review Group

*NCC/31/AUG 95
 JULY*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon.-US GLO Mon.
 WIT: Fd. Burnt Stump with Notch S21½°W 22.44'
 Fd. Burnt Stump scribed CL S46½°W 20.77'
 Fd. Burnt Stump N70½°W 37.27'
 Fd. Burnt Stump N82½°E 23.43'
 Nail NW side 18" Norway S42°W 163.77 (0°00'00" Horizontal angle and distance measured with SDM3E)
 Nail W. side 21" Norway S06°41'E 153.46 (311°19')
 Nail SW side 20" Norway S42°35'E 184.10 (275°25')
 Nail N. side 20" Norway S68°51'E 348.40 (249°09')
 Intersection of Trail Roads S66°42'E 90.40 (251°18') NOTE: All angles in brackets are horizontal angles measured to the right using SDM3E total station.

Signed by Marvin E. Myers

Date July 27, 1995

Surveyor's Michigan License No. 31600