

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T 26N R 2E	A - 3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 4 pg. 58

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED
 2 AUG 95 9:34 A.M.
 PATSY J. PETERS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on May 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|--|--|
| GLO-L. Clason May 1839
Mon-Post
WIT: 12" Y.Pine N60°W 6.66 chs.
4" Spruce S62°E 4.87 chs.
6" Spruce N51°E 5.21 chs. | GLO-G. Veal Oct. 1935
Mon-Fd. 4"x4" Post perpetuate
original by J. Randall 1887
Set Conc. Mon. with Brass
Tablet at point
WIT: 8" J.Pine S87½°W 67½ lks.
9" J.Pine S87½°W 125 lks. | G.A. Shadko 1958
Mon-US GLO Mon.
WIT: None given
Consumers Power Co. Oct. 1979
Mon-US GLO Mon
WIT: Cor. fence post West 1.0'
14" J.Pine ENE 94.28'
8" J.Pine NNE 57.64' |
| Fargo Engineering 1908-1909
Mon-Unknown
WIT: None given | G. Henning May 1941
Mon-US GLO Mon. | L.3, pg.425 Edwin J. McCombs May 10, 1984
Mon-Fd. Gov't Mon.
WIT: 1.00' NW of cor. fence post
14" J.Pine ENE 44.28'
8" J.Pine NNE 57.64' |
| C.O. Seeley May 29, 1912
Mon-Post
WIT: None given | G.D. Henning 1953
Mon-US GLO Mon. | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found US GLO concrete monument with brass tablet.
 Corner fence post with USFS location poster S50°E 1.00'
 And is accepted as a perpetuation of the original government corner.

APPROVED
 County Remonumentation
 Peer Review Group

*NCC/31/AUG 95
 JULY*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-US GLO Mon.
 WIT: Nail in E. face 7" J.Pine S15°W 44.05'
 Nail in N. face 9" J.Pine S70°E 52.28'
 Nail in E. face 5" J.Pine N05°E 20.64'
 Nail in S. face 3" J.Pine S75°W 10.37'
 Centerline N-S road East 18.60'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600