

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>Oscoda</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>A - 4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber 4 pg. 59

STATE OF MICHIGAN  
 OSCODA COUNTY  
 FILED  
 2 AUG 95 9:35 A.M.  
 PATSY J. PETERS  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on May 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |   |   |  |
|---|---|--|
| GLO-L. Clawon May 1839<br>Mon-Post<br>WIT: 5" Spruce S45½°W 17 lks.<br>5" Spruce N20½°W 24 lks.   | G.D. Henning 1953<br>Mon-US GLO Conc. Mon.<br>WIT: None given | L. 3, pg.88 F. King April 1986<br>Mon-Fd. Std. Co. corner N-S Rd.<br>WIT: Red top post East 33.00'<br>8" J.Pine S40°W 42.65'<br>½" Iron West 33.06'<br>12" J.Pine N63°W 19.80' |
| GLO-G. Veal Oct. 1935<br>Mon-No evidence set Conc. Mon.<br>wit 3½" Brass Tablet<br>WIT: 9" J.Pine N88°E 19½ lks.<br>5" J.Pine N25½°W 26½ lks.<br>Set by proportate distance | G.A. Shadko 1958<br>Mon-US GLO Mon.<br>WIT: None given        | L.3, pg.31 F.King<br>Mon-Fd. Std. Co. corner N-S Rd.<br>WIT: Red top post East 33.00'<br>8" J.Pine S40°W 42.65'<br>½" Iron West 33.06'<br>12" J.Pine N63°W 19.80'              |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found standard Oscoda County Monument in centerline North - South Road and accepted as the best available evidence of the position of the Original corner.

**APPROVED**

County Remonumentation  
 Peer Review Group

*NCC/31 AUG 95  
 JULY*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Mon-Std. Oscoda County Mon. in centerline N-S Rd.  
 WIT: Fd. USFS locate post S85°E 33.00'  
 Fd. ½" bar N85°W 33.06'  
 Fd. spike in S. face 12" J.Pine N63°W 19.80'  
 Fd. spike in W. face 8" J.Pine S40°W 42.65'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600