

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>26N</u>	R	<u>2E</u>	<u>A - 7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

Liber 4 pg. 62

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

2 AUG 95 9:35 A.M.

PATSY J. PETERS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-L. Clawson May 1839 Mon-Post WIT: 12" Aspen S85°W 4 lks. 12" Aspen N50°W 35 lks. 10" Aspen N78½°E 24 lks. 12" Aspen S75°E 26 lks.	C.O. Seeley Sept. 21, 1914 Mon-Fd. stake by Randall (iron bar at stake) WIT: NBT Balsam N19°W 1.10 chs. Stone 2' dia. S26½°E 40 lks.	L.2, pg.114 N. Caldwell April 23, 1969 Mon-Fd. US GLO Mon. in C, E-W & N roads WIT: Guy Pole S68°W 93.40' 18" W.Pine N37°W 49.90' Power Pole N68°W 83.40'
John Randall Dec. 28, 1887 Mon-Remark Post Fd. both USBT'S WIT: 4" Fir N19°W 1.10 chs.	GLO-G. Veal Oct. 1935 Mon-Fd. Iron Bar Set by Randall 1887 from both original BT'S set at that point Conc. Mon. with Brass Tablet WIT: 16" Balsam N19°W 109½ lks.	L.2, pg. 428 N. Caldwell July 26, 1977 Mon-Fd. US GLO Mon. WIT: ½" Bar & Cap S45°E 46.00' 18" W.Pine N30°W 49.10' ½" Pipe N45°W 46.60' S. edge of E-W road South 8.0'
C.O. Seeley May 29, 1912 Mon-Unknown WIT: None given	MSHD MKW 1958 Mon-Conc. Mon. ½" Iron WIT: Guy Pole S68°W 93.37' Power Pole N68°W 83.41' 18" W.Pine N37°W 49.85'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" Bar in Monument Box. Replaced ½" x 18" bar and cap with 5/8" x 30" bar and standard Oscoda County cap. And is accepted as a perpetuation of the original government corner.

APPROVED
 County Remonumentation
 Peer Review Group

NCC/31/106 95
JULY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-5/8" Bar with Standard Oscoda County cap in pavement box
 WIT: Centerline E-W road North 5.50'±
 Centerline road North is East 3.50'±
 Nail & Tag SW side utility pole N60°W 83.41'
 Nail 25" W.Pine N39°W 49.85'
 Nail & Tag Guy Pole S75°W 93.37'
 5½" W.Pine N47°E 77.45'



Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

Date July 28, 1995