

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda (County)	Located in:	Corner Code #
1. Public Land Survey	T 26N R 2E	A - 8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ R _____	_____
	S _____ R _____	_____
3. Miscellaneous Property in Section	S _____ R _____	_____
	S _____ R _____	_____

Liber 4 pg 63

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

2 AUG 95 9:36 A.M.

PATSY J. PETERS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 4, 1995,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO-L. Clawson May 1839
 Mon-Post
 WIT: 14" Maple S39½°W 38 lks.
 24" Maple N70°W 8 lks.

John Randall Dec. 27, 1887
 Mon-Set Post
 WIT: 7" Sugar S35°W 97 lks.
 20" Sugar N88°E 76 lks.

GLO- G. Veal Oct. 1935
 Mon-Accepted intersection of fences & G
 road extended Set Conc. Mon. with
 Brass Tablet
 WIT: 8" ELM S88°E 51 lks.
 13" Maple N72°W 73 lks.
 MSHD N. Caldwell 1958
 Mon-GLO Mon. & Brass Tablet
 WIT: 22" Elm N88°W 152.25'
 20" Elm N30°W 123.05'
 8" Tri. Ash S66°E 93.00'

L.1, pg.116 N. Caldwell Sept. 25, 1971
 Mon-Unknown
 WIT: None given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Oscoda County Standard Monument 24.7'± West of centerline M-72 in shoulder of road. Accepted as a careful and faithful establishment of the position of the corner.

APPROVED

County Remonumentation
 Peer Review Group

*NCC/31 AUG 95
 JULY*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Oscoda County Std. Mon.
 WIT: Fd. USFS location marker post; placed nail in N. face N81°W 55.62'
 Top center Conc. R/W marker post N37°W 52.47'
 South end Conc. culvert N30°E 91.55'
 Nail S. face 5" W.Pine S50°E 78.10'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600