

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|--------|
| 1. Public Land Survey | T 26N R 2E | A - 12 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Liber 4 pg. 67

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

2 AUG 95 9:37 A.M.

PATSY J. PETERS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 5, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-L. Clawson May 1839 L.1, pgs. 121 & 122 Larry Cavanagh Oct. 31, 1973
 Mon-Post Mon-GLO Mon. & Brass Cap
 WIT: 10" Spruce S28°W 17 lks. WIT: 10" J.Pine S17°W 10.40'
 12" Spruce N49°W 16 lks. 8" J.Pine N57°W 22.40'

GLO-Guy Veal 1935
 Mon-Set Conc. Mon. by proportionate distance
 WIT: 4" J.Pine N75½°E 30 lks.
 12" J.Pine N27°W 23½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found US GLO placed nail along side on fence line West; corner fence post is East 4.20'. Accepted US GLO monument as a careful and faithful establishment of the position of the corner.

APPROVED

County Remonumentation
 Peer Review Group

*NCC/31/0695
 JULY*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-US GLO Conc. Mon. with Brass Cap placed 6" pole barn nail along side
 WIT: Nail NW face 5" J.Pine N59°E 7.02'
 Nail NE face 4" J.Pine N51°W 7.18'
 Nail E. face 5" J.Pine S62°W 37.64'
 Nail W. face 3" J.Pine S02°E 23.02'



Signed by Marvin E. Myers

Date July 28, 1995

Surveyor's Michigan License No. 31600