

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 pg 72

For corners in Oscoda <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 26N R 2E	B - 9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

2 AUG 95 9:38 A.M.

PATSY J. PETERS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|---|
| GLO-W. Coon July 1839
Mon-Post
WIT: 10" Y.Pine S45°W 25 lks.
14" W.Pine N74°E 18 lks. | L.2, pg.131 N.Caldwell June 3, 1961
Mon-Fd. US GLO pipe & cap
WIT: 5' South of road G
Fence line North
10" Oak N06°E 31.70'
14" Oak S45°E 39.60'
22" Oak N40°E 48.50' | L.3, pg.116 N. Caldwell Sept. 1979
Mon-Unknown
WIT: Iron North 33.00' |
| US GLO-G. Veal Oct. 1935
Mon-Accept road & fence lines
Set conc. Mon. with
Brass Tablet
WIT: 6" B.Oak N06°E 48 lks.
8" B.Oak S45½°E 60 lks. | L.1, pg.205 N. Caldwell July 1972
Mon-Unknown
WIT: None given | Gary Wilson Sept. 21, 1992
LCRC L.3, pg.257
Mon-Fd. GLO Mon.
WIT: 4' South of G E-W Road
5" R.Pine N41°E 59.38'
8" R.Pine S48°E 84.25'
10" R.Pine S29°W 125.55'
Triple Maple N08°W 106.39' |
| S.J.E. Lucas, Jr. Aug. 21, 1947
Mon-US GLO Mon.
WIT: None given | L.1, pg.487 N. Caldwell Mar. 27, 1974
Mon-Unknown
WIT: None given | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found US GLO Brass Cap monument with iron. Accepted as the best available evidence of the re-establishment of the original corner.

APPROVED

County Remonumentation
 Peer Review Group

NCC/31 ~~706~~ 95
 JULY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-US GLO concrete monument
 WIT: 5" R.Pine N41°E 59.38'
 8" R.Pine S48°E 84.25'
 10" R.Pine S29°W 125.55'
 West edge carsonite post S07°W 17.18'
 USFS Survey Coordinates
 Lat 44°37'23" .80041
 Long 84°14'29" .16240



Signed by Marvin E. Myers Date July 28, 1995

Surveyor's Michigan License No. 31600