

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>B - 13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber 4 pg. 74

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED
 2 AUG 95 9:39 A.M.
 PATSY J. PETERS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Marvin E. Myers, in a field survey on July, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| GLO-L. Clawson May 1839
Mon-Post
WIT: 5" Spruce Pine N37°E 11 lks.
6" Spruce Pine N47°W 15 lks. | C. Seeley Sept. 1914
Mon-Set by proportional measurement
Mon. unknown
WIT: 8" B.Oak S10°E 82 lks. |
| GLO-Guy Veal 1924
Mon-Set 1"x36" Iron Pipe
with Brass Cap
WIT: 8" J.Pine N50°45'E 96 lks.
6" J.Pine N52°45'W 63 lks. | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x36" Iron pipe with brass cap lying down 33.00 feet East of B-1, T25N, R2E. Appears to have been dislodged during area tree planting operations of U.S.D.A. (Forest Service). Reset 1"x36" USGLO monument with brass cap on Township line 33.00 feet East of B-1, T25N, R2E and accepted as a careful and faithful establishment of the position of the corner.

APPROVED
 County Remonumentation
 Peer Review Group

*NCC/31 #16 95
 JULY*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon- 1"x36" USGLO pipe with brass cap.
 Wit- Nail N. side 6" J. Pine S56°W 29.49
 Fd Dock spike W. side 8" J. Pine N10°W 61.64
 Centerline E-W trail road North 23'±
 Nail NW side 7" J. Pine N46°E 70.42
 Closing corner B-1, T25N, R2E is West 33.00



Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

Date July 28, 1995