

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Oscoda
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 26N R 2E C - 1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Liber 4 pg 136

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

26 NOV 96 2:44 P.M.

Register of Deeds Stamp & File Number

REGISTER OF DEEDS

	A	B	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 27, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Wm. Coon July 1839 Mon-Set Post WIT: 8" Aspen S62 3/4°W 17 lks. 16" Aspen S78°E 11 lks. SE Cor. Sec. 31, T27N, R2E East 23 lks.	Guy Veal Oct. 2, 1935 Mon-Fd. 1" iron pipe in road Set 3 1/2" dia. Brass Tablet in 6" dia. x 24" conc. cylinder WIT: Fd. SW Cor. Sec. 31, T27N, R2E East 23 lks. 5" Double Elm S67 1/2°W 94 lks.	Liber 3, pg. 11 Larry Beaugard Apr. 10, 1979 Mon.-Fd. 2" pipe 1' below road surface raised with 3" bar & RLS cap WIT: 15" Elm stump N45°E 64.85' 5" TW. J. Pine N30°E 58.40' 12" Elm stump N65°E 98.65' Fd. SE Cor. Sec. 31, T27N, R2E East 15.46' Set DNR post & tab South 33.00'
Wm. Fargo 1908-09 Mon.- WIT: Fd. stump badly mutilated said to be witness	George Henning June 7, 1941 Mon.-Fd. US GLO mon.	Liber 3, pg. 423 Edwin McCombs Oct. 1979

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar & cap
 Found 12" Elm stump N65°E 98.65'
 And is accepted as a careful and faithful perpetuation of the position of the original corner
 Closing Section Corner Sections 5 & 6, T26N, R2E

APPROVED
 County Remonumentation
 Peer Review Group

*NCC
 16 NOV 96*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced record 1/2" Bar with Standard Oscoda County Mon. Std. Cor. East 15.80(M) 15.18(R)
 WIT: Nail E. side DNR post N35°E 36.32'
 Nail S. side 7" Poplar N72°E 95.50'
 Nail W. side 7" Poplar S42°W 38.91'
 Nail W. side DNR location post S09°W 32.85'



Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

Date Sept 7, 1996

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

**SURVEY &
 REMONUMENTATION**
 MAR 19 1997
 COMMISSION