

**SURVEY &
REMONUMENTATION**

SEP 29 1994

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T 26N R 2E	C - 4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

L 3 Pg 269

STATE OF MICHIGAN
OSCODA COUNTY
FILED

14 SEP 94 11:05 A.M.
Register of Deeds Stamp & File Number

PATSY J. PETERS
REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-July 1839 Coon Mon-Post WIT: 4" Spruce Pine N84°E 12 lks. 2" Spruce Pine N15°W 5 lks.	GLO-1935 Guy Veal Mon-3 1/2" Brass Tablet in 6" Conc. Mon. WIT: 7" B.Oak S61 1/2°E 103 lks.
Sept. 1885 J.Randall Mon-Post WIT: Cor. Fence Post S82°W 33 lks. Cor. Fence Post S82°E 56 1/2 lks.	LCRC May 1964 R.Griffin Mon-US GLO Fd. Corner 1.5' below surface WIT: 10" Dock Spike in SE side 11" R.Pine N45°E 177.05' Angle Iron East 49.57' 5"x7' Cedar Post East 50.00' 10" Dock Spike in SW side 12" B.Oak S61 1/2°E 68.35 (GLO) 40 Penny Spike & Shinner NW side Telephone Pole S39°W 23.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Bar at surface verified position by measurement to accessories of record and is accepted as a careful and faithful reestablishment of the position of the original corner. Excavated 4 feet below surface found no remains of US GLO Monument.

APPROVED

County Remonumentation
Peer Review Group

*NCC
27 AUG 94*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Set Std. Oscoda County Monument.
WIT: 4" Pole Barn Nail SW side Power Pole N45°W 64.79'
Fd. Angle Iron East 49.57'
Fd. 5" Cedar Post East 50.00'
4" Polebarn Nail East side 14" Norway N10°W 77.47'
Fd. Dock Spike in SW side of 12" (now 19") B.Oak S61 1/2°E 68.35'



Signed by Marvin E. Myers

Date Aug. 23, 1994

Surveyor's Michigan License No. 31600