

**SURVEY &  
REMONUMENTATION**

SEP 29 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

L 3 Pg 277

For corners in

| Oscoda<br>(County)                    | Located In: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey                 | T 26N R 2E  | C - 12        |
|                                       | T R         |               |
|                                       | T R         |               |
|                                       | T R         |               |
| 2. Property Controlling<br>in Section | S T R       |               |
|                                       | S T R       |               |
| 3. Miscellaneous<br>Property in Sec.  | S T R       |               |
|                                       | S T R       |               |

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

14 SEP 94 11:07 A.M.

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Marvin E. Myers, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO-July 1839 Coon  
Mon-Post  
WIT: 4" Spruce Pine N39½°W 17 lks.  
6" Spruce Pine S54°E 27 lks.

GLO-Oct. 1935 Guy Veal  
Mon-3½" Brass Tablet in 6" Conc.  
WIT: J.Pine N09°E 41 lks.  
J.Pine S76½°W 47 lks.  
(no evidence of corner, set by proportionate distance)

L.2, pg.133 1969 N.Caldwell  
Mon-Fd. US GLO Mon  
WIT: C N-S Road East 62.30'

April 1911 C.O. Seeley  
Mon-Set Post

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 6" Concrete Monument with 3½" Brass Tablet. Verified position by measurement to accessories of record and accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon-6" Conc. Mon with 3½" Brass Tablet placed ½"x18" steel rebar along N. side for magnetic attraction  
WIT: Set Nail in N. side of USFS location post West 0.59'  
Set Nail in W. side-5" Poplar-North 14.25'  
Set Nail in SE side 6" J.Pine N45°E 7.65'  
Set Nail in E. side 5" B.Oak South 6.38'  
C N-S asphalt road 64.00'

**APPROVED**

County Remonumentation  
Peer Review Group

*NEC  
27 AUG 94*

Signed by Marvin E. Myers

Date AUG 24, 1994

Surveyor's Michigan License No. 31600