

SURVEY & REMONUMENTATION

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>26N</u> R <u>2E</u>	E - 1	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Liber 4 pg 138

STATE OF MICHIGAN
OSCODA COUNTY
FILED

26 NOV 96 2:46 P.M.

Patsy J. Peters
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on June 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1839 Coon
Mon. - Post intersection 11 lks. West
WIT: 4" Aspen S32°W 29 lks.
6" Aspen S46°E 29 lks.

1909 Fargo Eng.
Mon. - Unknown
WIT: 12" W. Pine S14°E 92½'

GLO - 1935 Guy Veal
Mon. - Brass tablet in 6" conc. mon. set at proportionate distance
WIT: 14" Norway S78½°E 149 lks.
9" Norway S12°W 163 lks.

May 1940 George Henning
Mon. - US GLO corner
WIT: None given

Liber 2, pg. 94
Norm C. Caldwell July 1965
Mon. - Fd. US GLO mon. raised with cabin spike flush with pavement
WIT: Power Pole N50°W 92.4'
½" bar South 33.0'
East 7.3' cor. Sec. 32 & 33
Liber 1, pg. 227
Distance between corner 8.18'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" bar in pavement box 7.13' distance between corners
And is accepted as a careful and faithful reestablishment of the position of the original corner
Closing Corner Sections 4 & 5, T26N, R2E

APPROVED

County Remonumentation
Peer Review Group

NCC
16 Nov 96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced record ½" Bar with Standard Oscoda County Monument in pav't box
WIT: Nail in cor. Fence Post S81°W 127.66'
Nail in W. side 3" Thornapple N32°W 62.30'
Nail NW side Utility Pole N55°E 74.51'
Nail E. side Utility Pole S01°W 45.15'



Signed by Marvin E. Myers

Date September 7, 1996

Surveyor's Michigan License No. 31600