

**SURVEY &
REMONUMENTATION**

SEP 29 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

L3 Pg 288

STATE OF MICHIGAN
OSCODA COUNTY
FILED

14 SEP 94 11:09 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

For corners in

Oscoda (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>E - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on July 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-July 1839 Coon Mon-Post WIT: 8" Hemlock S16°E 27½ lks. 6" W.Birch S66½W 34½ lks.	GLO-1935 Guy Veal Mon-Fd 1½" Pipe replaced with 3½" Dia. Brass Tablet WIT: 8" Poplar N52½°E 63½ lks. 8" Poplar S22½°E 97½ lks. 4" Poplar S71½°W 43 lks. 11" J.Pine N46°W 94 lks.
May 1914 C.O.Seeley Mon-Fd. old Stake Set 1½"x24" Pipe WIT: NBT 20" W.Pine Stump N28½°E 33½ lks.	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 6" Conc. US GLO 1935 Monument with 3½" Dia. Brass Tablet at fence corner. Old fence line East and South and North. Verified position by measurement to accessories of record and is accepted as careful and faithful perpetuation of the position of the original corner.

APPROVED

County Remonumentation
Peer Review Group

*NCC
27 AUG 94*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-6" Dia. Conc. US GLO Monument with 3½" Dia. Brass Tablet placed ½"x18" rebar along North edge for magnetic attraction
WIT: Fd. Spike in NW side 8" Tw. Maple S40°W 16.60'
Fd. Spike in South side with USFS Tag 10" Maple N75°E 51.85'
4" Polebarn Nail NE side at base of 7" W.Birch N45°W 14.42'
4" Polebarn Nail in West side 12" Poplar N04°E 39.20'



Signed by Marvin E. Myers

Date Aug 23, 1994

Surveyor's Michigan License No. 31600