

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L. 4 Pg. 27

For corners in
OSCODA
(County)

	Located In:	Corner Code #
	BIG CREEK TWP.	
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
OSCODA COUNTY
FILED

15 NOV 94 11:03 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

APPROVED

County Remonumentation
Peer Review Group

N.C. Caldwell
11/8/94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frederick J. King, in a field survey on June 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5 1/4 CORNER COMMON TO SECTIONS 9 & 16

- July 1839 - Orig Post set by Lewis Clason, D.S. - On File - Reg of Deeds - N76W - Spr Pine - 3.30' (5 lks)
S64W - Spr Pine - 5.28' (8 lks)
- 1935 - USGLO Mon set by Guy R. Veal, US Cad Eng - On File - Reg of Deeds - N88E - J. Pine - 31.02' (47 lks)
Set by Prop. Meas. - No Original Evidence Found S45E - J. Pine - 66.66' (101 lks)
- Feb. 1968 - COUNTY CORNER REGISTRY - by N.C. Caldwell, PS #12018 - N88E - 8" J. Pine - 31.0'
End Rec USGLO Mon - Rec Bk. 2, Pg. 100 S45E-12" J. Pine - 66.7'
- Jan. 1974 - Cor used by N.C. Caldwell, PS #12018 - NO CORNER DESCRIPTION - NO WITNESSES
Act #132 - Rec. L. 1, Pg. 451
- May 1975 - Cor used by N.C. Caldwell, PS #12018 - NO CORNER DESCRIPTION - NO WITNESSES
Act #132 - Rec L. 2, Pg. 166
- Jan. 1978 - Cor used by N.C. Caldwell, PS #12018 - NO CORNER DESCRIPTION - NO WITNESSES
Act #132 - Rec. L. 2, Pg. 575

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found Rec USGLO Mon \pm 7' S. of C.L. of E-W 2-Track Trail, with USFS Post along side
Iron Alongside Area has been recently Clear Cut - No Record Witnesses Fnd
No 1839 Witnesses Fnd
No 1935 Witnesses Fnd

This Corner was approved by the Oscoda County Peer Review Comm., as the Best Available Evidence of the Re-Establishment of the Original Corner on July 15, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Rec USGLO Mon. - Corner is at Fence Corner of N-S Fence & Fence to East
Iron Alongside Corner is \pm 7' South of C.L. of E-W 2-Track Trail
NORTH - 11.4' - S. Face of Northerly Steel Gate Post
N.45^oE. - 26.37' - Set Tag in NW Sd of 12" Oak
N.80^oE. - 39.96' - Set Tag in N. Sd of 6" R. Pine
S.35^oW. - 0.55' - Face of USFS Post
S.40^oW. - 27.31' - Set Tag in NW Sd of 5" R. Pine
N.60^oW. - 22.90' - Set Tag in NE Sd of 8" R. Pine

NOTE: Witness BTS were marked with Db1 Headed Nails with I.D. Tag #25852



Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date 11-4-94