

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

L. 4 Pg. 33

For corners in

OSCODA (County)	Located In: BIG CREEK TWP.	Corner Code ##
1. Public Land Survey	T 26N R 2E	G-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

15 NOV 94 11:06 A.M.

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**APPROVED**  
County Remonumentation Peer Review Group  
*N.C.C. 8 NOV 94*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, FREDERICK J. KING, in a field survey on October 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
G-4 1/4 CORNER COMMON TO SECTIONS 9 & 10

- July 1839 - Original Post set by Lewis Clason, D.S. - - - - - N80E - W Pine - 13.86' (21 lks)  
On File - Reg of Deeds S80W - W Pine - 7.92' (12 lks)
  - 1935 - USGLO Mon set by Guy R. Veal, US Cad Eng - Set by Prop Meas - - - - - N66 1/2 E - Poplar - 33.66' (51 lks)  
No Original Evidence Fnd - On file - Reg of Deeds N36W - Poplar - 32.01' (48 1/2 lks)
  - Apr 1969 - COUNTY CORNER REGISTRY by N.C. Caldwell, RLS - - - - - Fnd GLO Mon  
Rec Bk 2, Pg. 99 N66E - 7" Poplar - 33.7'
  - Oct 1970 - COUNTY CORNER REGISTRY by N.C. Caldwell, RLS - Rec Bk 2, Pg 99  
Fnd GLO Mon - SAME WITNESSES AS Bk 2, Pg. 315 N36W - 14" Poplar Stump - 32.0'  
N26E - Tri Maple Clump - 16.4'  
S76W - Cherry Clump - 14.3'
- NO ACT 132 FOUND RECORDED FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 10-24-94 - Found Rec USGLO Monument - Iron Alongside  
N26E - 16.4' - Fnd Old Blaze & USFS Plate Scribed, D.N. -1976 - In Tri Maple (Rec 1969 & 1970)  
N45E - 0.7' - Face of USFS Post with Plate Scribed, D.N. - 1976  
S76W - 14.3' - Fnd Blaze in Cherry Stump (Rec 1969 & 1970)  
NO 1839 or 1935 WITNESSES FOUND

This Corner was approved by the Oscoda County Peer Comm., as a Careful and Faithful Establishment of the position of the Corner on November 1, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 10-24-94 - Record USGLO Mon - In Line with N-S Fnc (Sng Strand - Wd Post) - Iron Alongside  
N26E - 16.83' - Set Tag W sd of Tri Maple  
N45E - 0.7' - Face of USFS Post  
S70E - 27.84' - Set Tag N sd of 10" W. Pine  
South - 0.5' - Face of Wood Fence Post  
S05W - 50.39' - Set Tag E sd 15" Balsam  
S76W - 14.3' - Old Blaze in Cherry Stump  
N45W - 22.52' - Set Tag NE sd 5" Balsam



NOTE: Witness Bts were marked with Db1 Headed Nails with I.D. Tag #25852

Signed by Frederick J. King Date 11-4-94  
Surveyor's Michigan License No. 25852