

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

L. 4 Pg. 37

For corners in  
OSCODA

(County)

Located In:

BIG CREEK TWP

Corner Code ~~##~~

- |                                    |                         |       |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey              | T 26N R 2E              | 6-8   |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

15 NOV 94 11:07 A.M.

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**APPROVED**

County Remonumentation  
Peer Review Group

*NCL NOV 94*

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, FREDERICK J. KING, in a field survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1/4 CORNER COMMON TO SECTIONS 21 & 22

- July 1839 - Original Post set by Lewis Clason, D.S. - - - - - N75E - Aspen - 5.28' (8 lks)  
On File - Reg of Deeds S50E - Aspen - 13.20' (20 lks)
- 1935 - USGLO Mon set by Guy R. Veal, US Cad Eng - Fnd 6"x6" Wd Post, set S22 1/2 E - W Pine - 25.41' (38 1/2 lks)  
by C.O. Seeley - said 6"x6" Wd Post was set from BT by J. Randall S46 3/4 E - W Pine - 32.67' (49 1/2 lks)  
who reestablished Cor in 1885 from Orig BT - Replaced said 6"x6" S70W - Balsam - 17.16' (26 lks)  
Post with GLO Mon - On File - Reg of Deeds
- May 1940 - US Post Fnd by George D. Henning, RLS - No Witnesses - Rec Bk T26N-R2E
- Sept 1940 - GLO Mon Fnd by George D. Henning, RLS - No Witnesses - Rec Bk T26N-R2E
- Dec 1973 - Cor Used by N.C. Caldwell, RLS - No Cor Description - No Witnesses - Act 132 Rec L.1, Pg 436

NO ACT 74 FOUND RECORDED FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 10-21-94 - Found Rec USGLO Monument - - - - North 4.2' USFS Post  
Iron Alongside S47E - 32.2' (R32.67') Fnd Blaze in 40" W Pine (1935 BT)  
S25W - 41.0' - Fnd Spk & BT Plate by GLH in 24" W Pine (Not Recorded)  
N50W - 1.6' - Fnc Cor Post for Fnc to N & W  
No 1839 Evidence Found

This Corner was approved by the Oscoda County Peer Review Comm., as a Perpetuation of the Original Government Corner, on November 1, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 10-21-94 - REC:USGLO MONUMENT - - - - North - 4.2' - USFS Post  
Iron Alongside N35E - 9.19' @ Set Tag in SE sd 8" Maple  
S45E - 32.88' - Set Tag in SW sd 40" W Pine  
S25W - 41.10' - Set Tag above Fnd Spk in W sd of 24" W Pine  
N80W - 35.03' - Set Tag in S sd 15" Maple  
N50W - 1.6' - Face of Fnc Cor Post

NOTE: Witness BTs were marked with Db1 Headed Nails with I.D. Tag #25852



Signed by Frederick J. King Date 11-4-94  
Surveyor's Michigan License No. 25852