

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

L. 4 Pg. 39

For corners in

<u>OSCODA</u> <small>(County)</small>	Located In: <b>BIG CREEK</b>	Corner Code # <b>G-10</b>
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
OSCODA COUNTY  
~~RECORDED~~  
Filed  
15 NOV 94 11:08 A.M.  
  
PATSY J. PETERS  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

APPROVED

County Remonumentation  
Peer Review Group

NOV 94

I, FREDERICK J. KING, in a field survey on June 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
G-10 1/4 CORNER COMMON TO SECTIONS 27 & 28

- |  |                                     |
|--|-------------------------------------|
| July 1839 - Original Post set by Lewis Clason, D.S. - - - - -            | N37½W - Spr Pine - 10.56' (16 lks)  |
| On File & Reg of Deeds   | N15E - Spr Pine - 11.22' (17 lks)   |
| 1935 - USGLO Mon set by Guy R. Veal, US Cad Eng - Set by Prop Meas - - - | N72E - J Pine - 19.80' (30 lks)     |
| No orig Cor Evidence Fnd - On File - Reg of Deeds                        | S42½W - J Pine - 14.52' (22 lks)    |
| Oct 1970 - COUNTY CORNER REGISTRY - Rec Bk 2, Pg. 383 - - - - -          | Fnd GLO Mon                         |
| by N.C. Caldwell   | N83W - 11" R Pine - 66.9'           |
| NO ACT 132 FOUND RECORDED FOR THIS CORNER                                | N25E - 22" R Pine - 73.2'           |
|  | N72E - 6" J Pine Stmp - 19.8' (NBT) |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 6-9-94 Fnd Rec GLO Mon - - - - - N25E - 73.2' - Fnd Rec BT (1970)  
with USFS Post N83W - 66.0' - Fnd Rec BT (1970)  
0.5' N. No 1839 Wit Fnd  
No 1935 Wit Fnd

This Corner was Approved by the Oscoda County Peer Review Comm., as the Best Available evidence of the Re-Establishment of the Original Corner on July 15, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Found Rec USGLO Mon - Would Not Dep - Set I & C on S edge  
Cor is ± 75' S of Intersection of N-S 2 track  
with 2 track to SW & ± 9' E of N-S 2 track  
N25E - 73.20' - Set Tag in E sd 36" R Pine  
N45E - 7.60' - Set Tag in NW sd 15" R Pine  
S75E - 11.16' - Set Tag in N sd 6" W Pine  
N83W - 66.58' (R-66.9) Set Tag in N sd 24" R Pine - (This BT is ± 10' W of 2 track running SWrly)  
N35W - 0.75' - USFS Post

NOTE: Witness BTs were marked with Db1 headed Nails with I.D. Tag #25852

Signed by Frederick J. King  
Surveyor's Michigan License No. 25852

Date 11-4-94

