

# SURVEY & REMONUMENTATION

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

L.4 Pg. 43

COMMISSION

For corners in

OSCODA (County)	Located In: BIG CREEK TWP.	Corner Code # H-5
1. Public Land Survey	T 26N R 2E	H-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED  
15 NOV 94 11:10 A.M.  
PATSY J. PETERS  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

**APPROVED**

County Remonumentation  
Peer Review Group

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5				●									
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, FREDERICK J. KING, in a field survey on October 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-5 1/4 CORNER COMMON TO SECTIONS 10 & 15

July 1839 - Original Post set by Lewis Clason, D.S. - - - - -	N0½N - W Pine - 24.42' (37 1/2 ks)
On File - Reg of Deeds	S8½E - W Pine - 9.90' (15 1/2 ks)
1935 - USGLO Mon set by Guy R. Veal, US Cad Eng - Set by Prop Meas. - - - -	N10½E - Elm - 20.79' (31 1/2 ks)
No evidence of Orig Cor Fnd - On File - Reg of Deeds	S34E - Poplar - 16.17' (24 1/2 ks)
Oct 1970 - COUNTY CORNER REGISTRY - Rec Bk 2, Pg 317, by N.C. Caldwell, RLS. -	N10E - 8" Elm - 20.4' (USBT)
Mar 1976 - Cor used by N.C. Caldwell, RLS - No Cor Description - No Witnesses	S10W - 12" Maple - 17.3'
Act 132 - Rec L 2, Pg. 235-236	N65W - 10" Balsam - 41.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10-24-94 - Found Rec USGLO Monument - Iron Alongside  
USFS Post on N. sd with Plate scribed, D.N. 8-76  
N10E - 20.4' - Elm Stump (Rec 1935 & 1970)  
S10W - 17.3' - 24" Maple with USFS Plate Scribed D.N. 8-76 (Rec-1970)  
No 1839 Witnesses Found

This Corner was approved by the Oscoda County Peer Review Comm., as a Careful and Faithful Establishment of the Position of the Corner on November 1, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10-24-94 - Record USGLO Mon with USFS Post on N. sd. - Iron Alongside  
N10E - 20.4' - Blaze in Elm Stump  
N35E - 30.19' - Set Tag W sd 12" W. Pine  
S10W - 17.78' - Set Tag W sd 24" Maple  
S55W - 9.16' - Set Tag N sd 3" Balsam  
N15W - 11.28' - Set Tag E sd 15" W. Pine



NOTE: Witness BTs were marked with Db1 Headed Nails with I.D. Tag #25852

Signed by Frederick J. King

Date 11-4-94

Surveyor's Michigan License No. 25852