

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L. 4 Pg 45

For corners in

<u>OSCODA</u> <small>(County)</small>	Located In: BIG CREEK TWP	Corner Code ## H-9
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
OSCODA COUNTY
Filed

15 NOV 94 11:11 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

APPROVED

County Remonumentation
Peer Review Group

NOV 94
NOV 94

I, **Frederick J. King**, in a field survey on **October 10**, 19 **94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
H-9 1/4 CORNER COMMON TO SECTIONS 22 & 27

July 1839 - Original Post set by Lewis Clason, D.S. - - - - -	N75E - Beech - 5.28' (8 lks)
On File - Reg of Deeds	S50E - Aspen - 12.20' (20 lks)
1935 - USGLO Mon Set by Guy R. Veal, US Cad Eng - Set by Prop Meas - -	N46½W - Norway - 51.15' (77½ lks)
No evidence of orig cor fnd - On File - Reg of Deeds	S75½W - Norway - 62.70' (95 lks)
Sept 1940 - GLO Mon Fnd by George D. Henning, RLS - No Witnesses - Rec Bk T26N-R2E	
Oct 1971 - COUNTY CORNER REGISTRY - Rec Bk 2, Pg 384 - GLO Mon Fnd - - - -	-N47W - 18" R Pine - 50.0' (NBT)
by Norman C. Caldwell, RLS	N47E - 10" Twin Oak - 43.8'
NO ACT 132 FOUND RECORDED FOR THIS CORNER	S70W - 14" Oak - 65.3'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10-10-94 - Found Rec USGLO Monument - Would Not Dip - Set I&C on S. Side
 N47E - 42.4' (Rec-43.8') - Fnd Blace in Twin Oak (1971 BT)
 S50W - 1.1' - Face of USFS Post (1971)
 S80W - (Rec-S70W) - 65.0' - (Rec 65.3') - Fnd Blaze 20" Oak (1971 BT)
 N47W - 49.5' -(Rec:50.0') - Fnd Blaze & BT Plate in 30" R Pine (1935-1971BT)

No 1839 Evidence Found

This Corner was approved by the Oscoda County Peer Review Comm. as a Careful and Faithful Establishment of the Position of the Corner on November 1, 1994

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10-10-94 - Rec USGLO Monument - - - - -	N47E - 42.20' (Rec 43.8') - Set Tag in SE sd Twin Oak
With Iron & ID Cap #25852	S60E - 29.38' - Set Tag in SW sd 15" R Pine
on S. Side	S50W - 1.1' - Face of USFS Post
	S80W - 65.28' - Set Tag in N sd of 20" Oak
	N47W - 49.62' - Set Tag in NE sd 30" R Pine

NOTE: Witness BTs were marked with Dbl Headed Nails with I.D. Tag #25852

Signed by Frederick J. King

Date 11-4-94

Surveyor's Michigan License No. 25852

