

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L. 4 Pg. 46

For corners in

| | | |
|--|---------------------------------|-----------------------|
| <u>OSCODA</u> <small>(County)</small> | Located In: BIG CREEK | Corner Code <u>##</u> |
| 1. Public Land Survey | T <u>26N</u> R <u>2E</u> | <u>H-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
OSCODA COUNTY
FILED

15 NOV 94 11:12 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

APPROVED

County Remonumentation
Peer Review Group *NOV 94*

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, FREDERICK J. KING in a field survey on October 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-11 1/4 CORNER COMMON TO SECTIONS 27 & 34
 - July 1839 - Original Post set by Lewis Clason, D.S. - - - - - N32E - Beech - 13.20' (20 lks)
On File - Reg of Deeds
 - 1935 - USGLO Mon Set by Guy R. Veal, US Cad Eng - Set by Prop Meas - - - S22E - Sugar - 12.54' (19 lks)
No evidence of orig cor fnd - On File - Reg of Deeds
 - Dec 1968 - COUNTY CORNER REGISTRY - GLO Mon fnd by N.C. Caldwell, RLS - - - N27 1/2 E - Poplar - 28.71' (43 1/2 lks)
Rec Bk 2, Pg 126
 - Set USFS Post Alongside
No Ref. Available

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 10-10-94 - Fnd Rec USGLO Mon - - - - - N50W - 1.2' - Face of USFS Post
Iron Alongside
No 1839 or 1935 Witnesses Found
No Witnesses marked in 1968

This Corner was Approved by the Oscoda County Peer Review Comm. as a Careful and Faithful Establishment of the Position of the Corner on November 1, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 10-10-94 - Rec USGLO Monument - - - - - N80E - 13.77' - Set Tag in N sd 3" Pine
Iron Alongside
- S15W - 17.94' - Set Tag in E sd 6" Elm
- N75W - 26.23' - Set Tag in S sd 6" Poplar
- N50W - 1.2' - Face of USFS Post
- N30W - 27.27' - Set Tag in E sd 4" Elm

NOTE: Witness BTs were marked with Db1 Headed Nails with I.D. Tag #25852

Signed by Frederick J. King

Date 11-4-94

Surveyor's Michigan License No. 25852

