

**SURVEY &
REMONUMENTATION**

MAR 19 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Liber 4 Pg 142

STATE OF MICHIGAN
OSCODA COUNTY
FILED

26 NOV 96 2:57 P.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T 26N R 2E	I - 1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1839 L. Coon Mon.-Post WIT: 18" Birch S02°E 20 lks. 18" Cedar S08°W 34 lks. I measured closing 4 lks. E of post 1909 Fargo Eng. Mon.-Fd. corner & Bearing Trees made by Randall (Note: did not find Randall's notes)	July 1932 G.D. Henning Mon.-Fd. Seeley NBT'S & Iron Pipe (Note: did not find Seeley notes) WIT: NBT 12" Beech S22°W 73.5' NBT 7" Elm S26°E 64.2'	Liber 2, page 90 N.C. Caldwell Mon.-Fd. US GLO mon. raised with RR spike & RLS Cap flush with pavement WIT: Standard cor. West 2.6'
	US GLO 1935 Guy Veal Mon.-Set 3 1/2" Brass Tablet in 6" conc. Mon. at proportionate distance WIT: 10" Elm S34°E 96 lks. Marked NBT 13" Dead Beech S23 3/4°W 113 lks. marked NBT 6" Elm S11 1/2°W 102 lks. Closing Cor. is 0.04 chs. East of Standard Cor.	Liber 4, page 341 Nov. 1988 F. King Mon.-Fd. cor. in mon. box 2.6' East of SE cor. Sec. 34

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar in pavement box and is accepted as a careful and faithful reestablishment of the position of the original corner. Corner is common to Sections 34 and 35 T26N, R2E

APPROVED

County Remonumentation
Peer Review Group

*NCC
16 Nov 96*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument - Replaced with a Standard Oscoda County Monument in pav't box.
WIT: Set nail E. side 5' above ground 6" Elm SE 46.66'
Fd. nail & tag SE side P.Pole N52°E 58.20'
Nail side Cedar N19°E 37.10'
Nail NW side 4" Elm S76°W 88.20'



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date September