

**SURVEY &  
REMONUMENTATION**

MAR 19 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

*Liber 4 pg 144*

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

26 NOV 96 2:59 P.M.

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in <u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>K - 1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 28, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO 1839 Coon Mon.-Post WIT: 15" Elm S68½°W 20 lks. 14" Maple S62½°E 6 lks. Sept. 14, 1916 E.S. Houghton Mon.-Set ½" pipe County Survey Notes Book 3, pg.50 Mon.-Pd. ½" pipe place by Houghton WIT: NRT 24" Elm S34°E 104.5' NBT 10" Aspen S43°W 76.4'	US GLO 1935 Guy Veal Mon.-Set 3½" brass tablet in 6" conc. mon. 0.21 cor. 35 & 36 T27N, R2E WIT: 24" Elm S40 3/4°E 173 lks. 8" Poplar S34½°W 104 lks. 10" Poplar S58½°W 137 lks.	Liber 193, page 8278 Oct. 1993 T. Lapham Mon.-Pd. iron in mon. box WIT: G E-W road East 12.81' SE Cor. Sec. 35, T27N, R3E
---	--	--

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found ½" bar in pavement box  
And is accepted as the best available evidence of the position of the original corner Township corner T26N, R2E

**APPROVED**

County Remonumentation  
Peer Review Group

*NCC  
16 Nov 96*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Replaced record ½" Bar with a standard Oscoda County Monument in pav't box  
WIT: PK nail top guard rail post N30°W 34.05'  
PK nail top guard rail post N72°E 39.68'  
PK nail top guard rail post S55°E 37.20'  
PK nail top guard rail post S53°W 24.10'



Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600

Date Sept. 7, 1996