

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 Pg. 16

For corners in

<u>Oscoda</u> (County)	Located In: <u>Big Creek Twp.</u>	Corner Code ## <u>(K-8)</u>
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>(K-8)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
OSCODA COUNTY
FILED

3 NOV 94 9:37 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry G. Beauregard in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K-8) Wood $\frac{1}{4}$ section post set by William R. Coon in 1839.
Wits: 20" Y. Pine N 38-3/4° E 3 links 10" Spruce Pine S 15 1/4° W 39 links
Guy R. Veal in 1935 found by proportionate distance that there is no remaining evidence of the original post or B.T. Set a brass tablet, 3 1/2" diam., 3" stem in conc. mon. 24" long, 6" diam., 18" in ground for $\frac{1}{4}$ Section corner with top marked Secs. 23 & 24. Government Deputy Surveyor. Dependent Resurvey of T 26 N, R 2 E. Wits: (6" J. Pine S 23-3/4° E 126 links) (14" J. Pine S 29 1/2° W 195 links).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-8) Found U.S. GLO mon. 2" above ground in good condition with USFS post alongside. Note: This corner is 12± S. of two track trail road running NE-SW. Placed 1/2" x 18" bar alongside monument.

APPROVED
County Remonumentation
Peer Review Group
NCC/31 OCT 94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-8) $\frac{1}{4}$ corner common to Sections 23 and 24, T 26 N, R 2 E
U.S. GLO monument 2" above ground in good condition with USFS post alongside, and is accepted as a careful and faithful reestablishment of the position of the original corner. (Placed 1/2" x 18" bar alongside monument).
9" B. Oak S 65° W 9.95' Norway S 40° W 29.62'
7" Norway N 25° W 43.95' 9" Norway N 20° E 42.8'
Placed blaze, 20 penny spike & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard Date 10/21/94
Surveyor's Michigan License No. 18654