

**SURVEY & REMONUMENTATION**

MAR 19 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>L - 1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Liber 4 pg. 145*

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

26 NOV 96 3:00 P.M.

PATSY J. PETERS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	10	9	8	7	6	5	4	3	2	1		
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Sept. 14, 1916 E.S. Houghton Mon.-1 1/2" pipe	County Survey Book 3 (G.D. Henning) Mon.-Fd. sq. stake center of Hwy evidently set by Houghton WIT: NBT's 7" Elm S19°E 36.5' 5" Birch S45°W 59.7'	Nov. 1971 N. Caldwell Mon.-US GLO Mon. WIT: S 1/2 Sec. 36, T27N, R2E US GLO East 6.95'
US GLO 1935 Guy Veal Mon.-Set brass tablet in conc. mon. proportionate distance WIT: 8" Elm S28 3/4°E 59 1/2 lks. 7" Birch S40°W 83 1/2 lks.	June 1957 S. Ernest Lucus Mon.-Fd. 1/2" bar raised with 1/2" pipe	Date Unknown N. Caldwell Mon.-Fd. US GLO mon. raised to gravel surface with 1/2" bar & 1" angle iron flush with pavement surface
	July 1965 N. Caldwell Mon.-US GLO Mon. WIT: S 1/2 Sec. 36, T27N, R2E US GLO East 6.95'	Liber 1, page 34 Dec. 29, 1972 N. Caldwell Mon.-Fd. US GLO mon. & raised with 1" angle iron WIT: East 7.0' S 1/2 Cor. Sec. 36, T27N, R2E
		Liber 4, page 288 Beg. 1988 F. King Mon.-Fd. 1" Iron WIT: 7.0' West of S 1/2 Cor. Sec. 36, T27N, R2E

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1/2" bar in pavement box  
S 1/2 Cor. Sec. 36, T27N, R2E is 6.95 feet East  
This position not established by original government survey.  
This monument is accepted as a careful and faithful determination of the position of the corner.  
Township corner T26N, R2E

**APPROVED**  
County Remonumentation  
Peer Review Group

*NCC  
16 NOV 96*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Replaced record 1/2" Bar with a standard Oscoda County Monument in pav't box  
WIT: Fd. spike W. side telephone pole S45°W 39.85'  
Fd. spike W. side 6" Ash S25°E 46.79'  
Fd. spike W. side 7" Elm N25°E 71.44'  
Fd. spike NE side power pole N49°W 69.50'



Signed by Marvin E. Myers Date Sept 4, 1996  
Surveyor's Michigan License No. 31600