

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 Pg. 23

For corners in

<u>Oscoda</u> (County)	Located In: Big Creek Twp.	Corner Code: #
1. Public Land Survey	T <u>26N</u> R <u>2E</u>	<u>(L-7)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
OSCEOLA COUNTY  
FILED

3 NOV 94 9:40 A.M.

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry G. Beauregard in a field survey on July, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (L-7) Wood  $\frac{1}{4}$  section post set by William R. Coon in 1839.  
Wits: 4" Spruce Pine S 25-3/4° W 19 links 4" Aspen N 81 $\frac{1}{2}$ ° E 19 links
- Guy R. Veal in 1935 found by proportionate distance that there was no remaining evidence of the original post or bearing trees. Set a brass tablet 3 $\frac{1}{2}$ " diam., 3" stem in conc. mon. 24" long, 6" diam., 18" in ground, for  $\frac{1}{4}$  Sec. cor. with top marked Secs. 13 and 24. Gov't Deputy Surveyor. Dependent Resurvey of T 26 N, R 2 E.  
Wits: (5" B. Oak S 80° W 45 links) (7" B. Oak N 39 $\frac{1}{4}$ ° W 54 $\frac{1}{2}$  links).
- George D. Henning P.S. #2240 in 1960 found GLO mon. Wits marked: (8" B. Oak S 80° W 29.7') (4" B. Oak N 39 $\frac{1}{4}$ ° W 36.0').
- Huston Kennedy P.S. #17623 in 1982 found GLO mon. no wits marked. Recorded L. 4, P. 155-162.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (L-7) Found U.S. GLO monument in good condition 3" above ground and red top post 1.5'± SE. Also placed  $\frac{1}{2}$ " bar alongside GLO monument.

**APPROVED**

County Remonumentation  
Peer Review Group

NCC/31 OCT 94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (L-7)  $\frac{1}{4}$  corner common to Sections 13 and 24, T 26 N, R 2 E  
U.S. GLO monument and red top post 1.5'± SE, and is accepted as a careful and faithful reestablishment of the position of the original corner. (Placed  $\frac{1}{2}$ " bar alongside monument).
- 9" Norway N 55° E 39.30' 8" Norway S 40° E 35.60'  
7" Maple in clump of three S 80° E 29.40' 7" B. Oak S 05° W 7.39'  
8" B. Oak S 84° W 29.30' (R) Henning wits., tag
- Placed blaze, 20 penny spike and P.S. Tag #18654 (typ)



Signed by Larry G. Beauregard Date 10/21/94  
Surveyor's Michigan License No. 18654