

OCT 08 1997

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 pg 192

For corners in

OSCODA (County)	Located In: MENTOR TWP.	Corner Code #
1. Public Land Survey	T26N R 3E	C-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
OSCODA COUNTY
FILED

3 OCT 97 12:04 P.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, FREDERICK J. KING, in a field survey on July 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- C-1 - CORNER COMMON TO SECTIONS 5 & 6
July 1839 - Original Post set by W.R. Coon, D.S. - S21°0W - 89 lks (58.74') - 8" Aspen - S52°0E - 47 lks (31.02') - 4" Asp
Pg 81
- Sept 1930 - GLO ReSurvey by G.R. Veal - Set 6"x24" Conc Mon & Brass Cap by Prop Dist - No Orig Evidence Found
On File @ Reg of Deeds - Pg 28 S44°E - 74½ lks (49.17') - 8" J Pine
Cor C-13 is 45.54' West S11°W - 46 lks (30.36') - 6" Poplar
- Jan 1971 - Act 132 by N.C. Caldwell, PS #12018 - No Cor Desc & No Wit - Shows Cor C-1 46.35' East of C-13
On File @ Huron Nat Forest Service
- Jan 1971 - Act 74 by N.C. Caldwell, PS #12018 - Fnd GLO Mon & Cap - Placed USFS Post alongside
S44°E - 48.8' - 10" J Pine S11°W - 30.4' - 10" Poplar (R) - WEST - 46.35' - Cor C-13 (27-3)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-1 - CORNER COMMON TO SECTIONS 5 & 6
FOUND GLO CONC MONUMENT & BRASS CAP with USFS POST ALONGSIDE -
S11°W - 30.4' (M) - Fnd Wit Plate in Dead Poplar
S44°E - 48.8' (M) - Fnd Wit Plate in Dead J Pine

APPROVED
County Remonumentation Peer Review Group
NCC
30 SEPT 97

This Corner Approved by County Peer Review on July 11, 1997, as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1 - CORNER COMMON TO SECTIONS 5 & 6
GLO MONUMENT WITH Re-Rod and UFSF Red Top Post Alongside
N25°E - 7.68' - Set S&T on SE side of 8" Birch
S44°E - 48.8' - To Blz on Dead J. Pine with Wit Plate
S15°E - 17.52' - Set S&T on W side of 6" Balsam
S11°W - 30.4' - To Blz on Dead Poplar with Wit Plate
WEST - 17.77' - Set S&T on N side of 15" Cedar
N15°W - 10.78' - Set S&T on E side of 20" Cedar
WEST - 46.48' (R-45.54' G. Veal & 46.35' N. Caldwell) GLO Mon & CAP @ Cor C-13 (27-3)

Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date Sept. 25, 1997