

OCT 6 8 1997

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Liber 4 pg. 194*

For corners in

OSCODA (County)	Located In: MENTOR TWP.	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>3E</u>	<u>E-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

3 OCT 97 12:06 P.M.

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, FREDERICK J. KING, in a field survey on July 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**APPROVED**  
County Remonumentation  
Peer Review Group  
*NCC  
SEPT 97*

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-1 - CORNER COMMON TO SECTIONS 4 & 5  
July 1839 - Original Post set by W.R. Coon, D.S. - S63°W - 16 lks (10.56') - 11" Spr Pine  
Int 18 lks (11.88') West of E-13 (27-3) S09°W - 22 lks (14.52') - 6" Spr Pine Pg. 73
- Sept 1930 - GLO ReSurvey by G.R. Veal - Set 6"x24" Conc Mon with Brass Cap by Prop Dist - On File @ Reg of Deeds  
Cor E-13 (27-3) is 11.88' EAST No Original Evidence Fnd - S23°E - 125 lks (82.50') 6" J Pine  
S8½°W - 67 lks (44.22') 9" J Pine
- Jan 1971 - Act 132 by N.C. Caldwell, PS#12018 - No Cor Desc - No Wit - On File @ Huron Nat Forest Service  
Shows E-1 West of E-13 (27-3)
- Jan 1971 - Act 74 by N.C. Caldwell, PS #12018 - No Witness to this Corner - Shows E-1 being 11.9' West of E-13 (27-3)  
E-13 (27-3) No Act 74 Found Recorded for this Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-1 - CORNER COMMON TO SECTIONS 4 & 5  
FOUND GLO CONC MONUMENT - BRASS CAP IS GONE - In West Bank of N-S gravel Road (Perry Creek Rd)  
With USFS Post 2' West EAST - 11.95' (M) - GLO Mon & Brass Cap @ Cor E-13 (27-3)

This Corner Approved by County Peer Review on July 11, 1997, as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-1 - CORNER COMMON TO SECTIONS 4 & 5  
GLO monument (Brass Cap Gone) with Re-Rod & Co. Re-Mon Cap on South Side on West Bank of N-S gravel road (Perry Creek Rd.)
- N70°E - 95.90' - Set S&T above Spk on NW side of 12" Oak
- S60°E - 76.77' - Set S&T above Spk on N side of 18" J. Pine
- S10°W - 47.30' - Set S&T on W side of 20" Oak
- N50°W - 1.38' - Set S&T on N side of USFS Red Top Post
- N50°W - 51.89' - Set S&T above Spk on NE side of 15" J. Pine
- EAST - 11.95' (R-11.88' G. Veal & 11.9' N. Caldwell) GLO Mon & Cap @ Cor E-13 (27-3)

Signed by *Frederick J. King*  
Surveyor's Michigan License No. 25852

Date Sept. 25, 1997