

REMONUMENTATION

OCT 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 pg 196

For corners in

OSCODA (County)	Located In: MENTOR	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>3E</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

3 OCT 97 12:08 P.M.

PATSY J. PETERS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **FREDERICK J. KING**, in a field survey on July 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-1 CORNER COMMON TO SECTIONS 3 & 4
 July 1839 - Original Post set by W.R. Coon, D.S. - S60°W - 413 lks (272.58') - 4" Spr Pine
 Pgs 68 -69 S71°E - 317 lks (209.22') - 4" Spr Pine
 Sept 1930 - GLO ReSurvey by G.R. Veal - Set 6"x24" Conc Mon & Brass Cap by Prop Dist.
 On File @ Reg of Deeds Pg 25 No Original Evidence Fnd
 Cor G-13(27-3) is 34.98' EAST S72½°E - 160 lks (105.60') - 8" J. Pine
 S23°W - 374 lks (246.84') - 10" J. Pine
 July 1979 - Act 132 by N.C. Caldwell PS #12018 - No Desc of G-1 - No Wit to G-1
 G-13(27-3) Rec. L. 3, Pgs. 100-101 G-1 is 34.9' WEST of G-13(27-3)
 Sept 1979 - Act 74 by N.C. Caldwell, PS #12018 - No Desc of G-1 - No Wit to G-1
 G-13(27-3) G-1 is 34.9' WEST of G-13(27-3)
 No Act 132 Fnd Recorded for G-1 No Act 74 Fnd Recorded for G-1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-1 CORNER COMMON TO SECTIONS 3 & 4
 FOUND GLO CONC MONUMENT & BRASS CAP. WITH USFS Post Alongside
 EAST - 34.95'(M) - Fnd GLO Conc Mon & Brass Cap

APPROVED

County Remonumentation
 Peer Review Group

*NCL
 30 SEPT 97*

This Corner Approved by County Peer Review, on July 11, 1997, as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1 CORNER COMMON TO SECTIONS 3 & 4
 GLO MONUMENT & BRASS CAP, WITH Pipe & USFS Red Top Post Alongside - †52' N of C.L. of E-W 2-track trail:
 N20°E - 6.08' - Set S&T on E side of 10" J. Pine
 N50°E - 43.46' - Set S&T on W side of 12" J. Pine
 S40°E - 22.85' - Set S&T on N side of 6" J. Pine
 N60°W - 13.11' - Set S&T on NE side of 8" J. Pine
 EAST - 34.95' - (R-34.98' G. Veal & 34.9' N. Caldwell) GLO Mon & Cap @ Cor G-13 (27-3)

Signed by *Frederick J. King* Date *Sept 25, 1997*
 Surveyor's Michigan License No. 25852