

REMONUMENTATION

OCT 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSCODA (County) Located In: MENTOR Corner Code # L-1
1. Public Land Survey T 26N R 3E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

LIBER 4 pg. 201

STATE OF MICHIGAN
OSCODA COUNTY
FILED

3 OCT 97 12:13 P.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, FREDERICK J. KING, in a field survey on July 2, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell L-1 is marked with a dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 NORTH 1/4 CORNER OF SECTION 1
Not Set on Original Government Survey
Sept 1930 - GLO ReSurvey by G.R. Veal - Set 6"x24" Conc Monument & Brass Cap by Prop. Dist.
On File @ Reg of Deeds Pg. 19-20 S26 1/2 °E - 51 lks (33.66') - 6" B. Oak
L-13 is 3.30' WEST S55 °W - 64 lks (42.24') - 6" B. Oak

No Act 132 Fnd Recorded for L-1
No Act 74 Fnd Recorded for L-1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 NORTH 1/4 CORNER OF SECTION 1
Found GLO Conc. Monument & Brass Cap. with USFS Post Alongside
Corner is ±1.8' West of Fence Cor Post (Fence to East & North)

APPROVED
County Remonumentation
Peer Review Group

NCC
30 SEPT 97

This Corner Approved by County Peer Review, on July 11, 1997 as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 NORTH 1/4 CORNER OF SECTION 1
GLO Monument & Brass Cap - ±1.8' West of Fence Corner Post (Fence to N & E)
N20 °E - 42.77' - Set S&T on W side of 15' Oak (Fnd Blz)
S75 °E - 2.15' - Set S&T on N side of Fence Corner Post (Fence to N & E)
S15 °W - 5.77' - Set S&T on W side of 10" Oak (Fnd Blz)
N60 °W - 22.25' - Set S&T on S side of 10" Oak (Fnd Blz & Spk on N side)
WEST - 3.30' - GLO Brass Cap & Pipe @ Corner L-13 (T27N-R3E)

Signed by Frederick J. King Date Sept. 25, 1997
Surveyor's Michigan License No. 25852