

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3
PAGE 68

For corners in

<u>Oscoda</u> <small>(County)</small>	Located In:	Corner Code: //
1. Public Land Survey	T <u>27N</u> R <u>1E</u>	A-10 A-12
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

FILED

At 11:10 o'clock A M

Date June 1, 1990

PATRICIA WRIGHT
Register of Deeds
Oscoda County, Michigan

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell in a field survey on March, 1990

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

(A-10) Original government survey did not establish this position.

(A-12) Original government survey did not establish this position.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-10) DNR mon. placed by K.J. Ostling, LS 10068 recorded in L. 1, pg. 177
 N14°E 120.05' 5" R. Pine
 S18°E 44.4' 6" J. Pine

(A-12) Placed by K.J. Ostling, LS 10068, Jan. 6, 1984, 5/8" bar w/LS 10068 cap
 N71°E 17.9' 6" J. Pine
 S40°E 43.5' 7" J. Pine
 East 12.9' Marker Post

NOTE: These are "closing corners" and do not control alignment of the Michigan Meridian.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-10) 1/4 cor. Sec. 30, T27N-R1E
 Fnd. DNR pipe & cap
 West 5' Carsonite Witness Post
 N14°E 120.1' 10" R. Pine (R)
 S18°E 44.5' 10" J. Pine (R)
 East 11.8' Red Top Post
 S15°W 48.2' 6" J. Pine

(A-12) 1/4 cor. Sec. 31, T27N-R1E
 Fnd. DNR 5/8" bar w/LS 10068 cap
 @ W. edge N-S trail 75'+ N. of
 Cherry Creek Rd. @ Co. Line
 West 5' Carsonite Wit. Post
 South 79.0' 1/2" bar in Rd. (R)
 N70°E 18.1' 8" J. Pine (R)
 S40°E 44.0' 8" J. Pine (R)
 East 12.9' Red Top Post

signed by _____ Date April 26, 1990

Surveyor's Michigan License No. 12218

