

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3  
 PAGE 12

For corners in

Oscoda (County) Located In: Corner Code: //

1. Public Land Survey T 27N R 1E B-13  
 T R  
 T R  
 T R

2. Property Controlling in Section S T R  
 S T R

3. Miscellaneous Property in Sec. S T R  
 S T R

FILED

At 11:14 o'clock A.M.

Date June 6, 1990

PATRICIA WRIGHT  
 Register of Deeds  
 Oscoda County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat  
 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell in a field survey on March 19 90 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B-13) Post set by Clason, May 16&17, 1839.  
 Forked Spruce Pine 10" N63°W .38 (25.08')  
 Forked Spruce Pine 8" N48 1/2°E .55 (36.30')

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-13) 6" conc. mon. w/brass cap placed by Guy R. Veal, Cadastral Engineer, 1937.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-13) S 1/4 cor. 31, T27N-R1E  
 Fnd. U.S.G.L.O. conc. mon. w/ brass cap dated 1937. And is accepted as a careful and faithful perpetuation of the position of the orig. cor.  
 North 0.5' Carsonite Witness Post S30°W 84.6' P. Pole  
 N10°W 25.6' 12" J. Pine East 41.7' N 1/4 Sec. 6, (GLO mon.)  
 S85°W 17.3' 6" N. Pine  
 S60°W 36.0' 5" N. Pine  
 N50°E 21.9' 6" J. Pine

igned by Norman C. Caldwell April 26, 1990

urveyor's Michigan License No. 12018

