

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

*LIBER 3*  
*PAGE 73*

For corners in

<u>Oscoda</u> <small>(County)</small>	Located In:	Corner Code <i>11</i>
1. Public Land Survey	T <u>27N</u> R <u>1E</u>	C-7 C-8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**FILED**  
 At 11:15 o'clock A M  
 Date June 6 1990  
 PATRICIA WRIGHT  
 Register of Deeds  
 Oscoda County, Michigan  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Norman C. Caldwell in a field survey on March 19 90

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

6. Description of original monument and accessories and/or subsequent restoration:

- (C-7) Post set by Coon, Dec. 14, 1839.  
 Y. Pine 8" N12°W .31 (20.46')  
 Y. Pine 8" S19°E .14 (9.24')
- (C-8) Post set by Coon, Dec. 14, 1839.  
 Dwarf Oak 4" S41°E .10 (6.60')  
 Y. Pine 7" N50 1/2°W .33 (21.78')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (by Caldwell)

- (C-7) 5/8" bar w/LS 12018 cap placed 8-18-66 to perpetuate a rec. corner.  
 N50°E 90.0' 5" Oak  
 S35°W 45.2' P. Pole  
 S15°E 59.4' 10" Oak  
 N40°W 77.0' 12" Oak
- (C-8) 1/2" bar placed by Henning, LS 2240, July 23, 1976, L. 1, pg 170  
 S75°E 14.2' 10" J. Pine  
 N63°E 13.6' 8" J. Pine

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (C-7) <u>Sec. cor. 17,18,19&amp;20, T27N-R1E</u><br>Fnd 5/8" bar w/12018 cap in CL<br>E-W pav't & N-S Rds. And is<br>accepted as a careful & faithful<br>perpet. of the position of orig. cor.<br>S45°W 40' Carsonite Wit. Post<br>N40°W 77.3' 14" Oak (R)<br>S35°W 44.1' P. Pole<br>N70°E 85.1' 12" Oak (R)<br>S45°E 91.3' 10" Oak | (C-8) <u>1/4 cor. 19&amp;20, T27N-R1E</u><br>Fnd. 1/2" bar w/12018 cap in E<br>wheel track of N-S Trail.<br>Accepted as a careful & faith-<br>ful reestablishment of the<br>position of orig. cor.<br>East 5' Carsonite Wit. Pos<br>N60°E 13.8' 12" J. Pine<br>S75°E 14.7' 12" J. Pine<br>N15°W 90.3' P. Pole<br>East 16.9' Red Top Post w/tag |
|---|--|

Signed Norman C. Caldwell Date April 26, 1990  
 Surveyor's Michigan License No. 12018

