

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3
 PAGE 14

or corners in _____

Oscoda Located In: _____ Corner Code: C-11
(County)

Public Land Survey T 27N R 1E _____ C-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

FILED
 At 11:17 o'clock A M
 Date June 6 1990
 PATRICIA WRIGHT
 Register of Deeds
 Oscoda County, Michigan
 Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Norman C. Caldwell in a field survey on March, 19 90
 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 (C-11) Post set by Coon, Dec. 13, 1839.
 Spruce Pine 12" N58 1/2°W 1.13 (74.58')
 Spruce Pine 4" S58°E .16 (10.56')

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (C-11) 1" bar placed by Henning, LS 2240
 DNR mon. placed by K.J. Ostling, LS 10068, April 19, 1977
 S25°W 26.45' 10" J. Pine
 S71°E 54.10' 10" R. Pine

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (C-11) Sec. cor. 29,30,31&32, T27N-R1E
 Fnd. DNR pipe & cap. Accepted as a careful & faithful reestablishment of the position of the original corner.
 North 1' Carsonite Witness Post N45°W 2.0' Red Top Post
 N65°W 6.2' 6" W. Pine
 S20°W 26.7' 14" J. Pine (old BT)
 S75°E 54.5' 16" N. Pine (Old BT)
 N60°E 17.7' 6" W. Pine

Witnessed by Norman C. Caldwell

Surveyor's Michigan License No. 12018

