

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda

(County)

Located In:

Corner Code #

Liber 5 pg 78

1. Public Land Survey

T 27 N R 2E  
T 27 N R 1E  
T R  
T R

A-3  
M-3

2. Property Controlling in Section

S T R  
S T R

3. Miscellaneous Property in Sec.

S T R  
S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Marvin E. Myers, in a field survey on June 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 1 and 12, T27N, R1E and Sections 6 and 7, T27N, R2E

GLO 1839 Lewis Clason, DS  
Mon - Post

Wit: 6" Dwarf Oak S30°W 92 lks  
8" Y. Pine S40°E 229 lks

GLO - 1839 William R. Coon, DS  
Mon - Post

Wit: 4" Spr Pine S76°E 233 lks  
4" Spr Pine N80°E 307 lks

July 1885 John Randall CS  
Mon: Remarkd Corner with

Cedar Stake; found 2 US BT  
Wit: 4" Spr. Pine S42°W 220 lks

14" Tamarack Post underpinning  
at SW cor. Of House N38½°E 141½ lks

County Surveyor's book page 132 no  
date or name possible G. Hennings

Mon - Found Seeleys NBT and Landslide  
and mortar

NBT: 10" Oak Crotch N56°30'E 176.6'  
4" Oak N67°30'W 55.5'

1968 Consumers Power Co. H. W. Dorcey  
Mon - Found Plow Point, replaced with "T -Iron

Wit: Tag in 4" bent J. Pine SW 36.35  
Blaze on 5" J. Pine NW 29.64

Nail in 5" J. Pine SE 63.55

Oct 1995 R. Mitchell, PS

Mon - Found "T" Iron 1' deep

Set spike S. side 5" J. Pine S54°W 45.28

Set spike N. side 13" Blazed Oak N77°W 31.97

Set spike N. side 7" Oak N72°E 47.23

Fd. Nail & tag in face 6" J. Pine S59°E 69.67

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner common to Sections 1 and 12, T27N, R1E and Sections 6 and 7, T27N, R2E

Found Land slide (Plow Point Tip) & "T" Iron along side in center line of Town Line Road and 7± North of E-W Penn Road; found nail S. side 8" J. Pine S57°W 35.39; found nail N. side 6" Oak N72°E 47.23; found spike N. side 13" blazed Oak N77°W 31.97. Accepted as the best available evidence of the position of the Original Government Corner. Replaced with 5/8"x34" Steel Rebar with Oscoda County Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner common to Sections 1 and 12, T27N, R1E and Sections 6 and 7, T27N, R2E

Mon - Standard Oscoda County Monument

Wit: Nail S. side 8" J. Pine S57°W 35.39

Nail in S. side 8" J. Pine 8" J. Pine N35°W 45.78

Face of DNR Post N30°W 53.79

Nail N. side 6" Oak N72°E 47.23

North edge of stop sign post S83°E 42.96

Nail N. side 4" J. Pine S35°E 63.75

APPROVED

County Remonumentation  
Peer Review Group

NCC  
27 JULY 00



Signed by

*Marvin E. Myers*

Date July 10, 2000

Surveyor's Michigan License No. 31600