

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: OSCODA Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 2 T 27N R 1E 6
 S 2 T 27N R 1E 7

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on December 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1											●	●	
2	6		5		4		3		2			1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

6- This corner position was not established during the original government survey.

7- This corner position was not established during the original government survey.



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

6- Established the Southwest corner of the Northeast quarter of the Northeast quarter if section 2 per standard B.L.M. instructions for subdivision of a section.

7- Established the Southeast corner of the Northeast quarter of the Northeast quarter of section 2 per standard B.L.M. instructions for subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6- Set 1" X 8' pipe with P.S. cap #33981

Wit: 8" White Pine S76°E 60.38'
 6" White Pine S70°W 69.32'
 9" Tamarack N38W 61.57'
 South end culvert N50°E 62.08'

7- Set 5/8" X 32" rod with P.S. cap #33981

Wit: 3" Spruce N07°E 26.22'
 6" Spruce S77°E 17.11'
 5" Spruce S42°W 14.56'
 6" Spruce S25°E 8.03'
 Fence corner west and south N62°W 32.5'

Signed by: _____

Carl T. Kiiskila

Date: _____

6-14-01

Surveyor's Michigan License No.: _____

33981