

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>OSCODA</u> (County)	Located In	Corner Code #	
1. Public Land Survey	T <u>27N</u> R <u>1E</u>	<u>I-12</u>	
	T <u>27N</u> R <u>1E</u>	<u>I-13</u>	
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl T. Kiiskila, in a field survey on January 16, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12 G.L.O. William R. Coon Dec. 1839
 Set quarter section post
 Wit: Spruce Pine 5 N60°W 5 Links
 Spruce Pine 6 S60°E 19 Links

I-13 G.L.O. Lewis Clawson May 1839
 Set post corner sections 34 and 35
 Wit: Yellow Pine 28 N72°W 1.11 chains
 Spruce Pine 4 N35°E 13 Links

Norman C. Caldwell RLS #12018 Found corner in monument box
 No description given.
 Wit: 6" J. Pine N62°W 49.8'
 5" Oak N84°E 57.0'

In the spring of 1937 Guy R. Veal did a dependent resurvey for the south line of section 35 T.27N., R.1E. for the Department of the Interior General Land Office. He re-established the corner from bearing trees marked by Consumers Power Co. surveyors in 1909. He marked the corner with a concrete monument with a brass cap.
 Wit: 12" Jack Pine N39 1/2°E 115 links
 8" Black Oak N37 1/2°W 113 links
 8" Jack Pine N20 3/4° W 206 links

The corner fall near the center of an improved highway which bears North and South.

Norman C. Caldwell RLS #12018 Found corner in monument box
 No description given.
 Wit: concrete monument West 33.0'
 Corner 2,3 (26/1) West 6.6'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

I-12 Found 1/2" capped rod in monument box.

I-13 Found 1/2" capped rod in monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Found 1/2" capped rod in monument box.
 Wit: 7" White Pine N85°W 37.84'
 8" White Pine N48°W 54.11'
 5" White Pine S54°E 63.72'
 6" Oak N87°E 57.30'
 Center line of N-S Blacktop Rd. East 1'±

I-13 Found 1/2" capped rod in monument box
 Wit: 4" White Pine S78°W 48.06'
 5" White Pine N62°W 47.04'
 8" Jack Pine N70°E 47.99'
 18" Oak S73°E 58.56'
 Centerline of N-S Blacktop Rd. East 1'±

Signed by: Carl T Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 6-14-01

