

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>OSCODA</u> (County)	Located In	Corner Code #	
1. Public Land Survey	T <u>27N</u> R <u>1E</u>	<u>K-13</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S <u>35</u> T <u>27N</u> R <u>1E</u>	<u>14</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on January 16, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-13 GLO Lewis Clawson May 1839  
 Set corner section post 35 and 36  
 Wit: Spruce Pine 12" N24°W 21 links  
 Spruce Pine 10" S09°E 12 links

14- This corner position was not established during the original government survey.

In the spring of 1937 Guy R. Veal did a dependent resurvey of the south line of section 35 T.27N., R.1E. for the Department of the Interior General Land Office. He found a 1 1/2" pipe for the S.E. corner of section 35 and replaced it with a concrete monument with a brass cap. Wit: 8" Jack Pine N56 1/4°E 84 links  
 10" Jack Pine N20 1/4°W 55 links  
 10" Jack Pine N58 1/4°E 85 links  
 8" Jack Pine N29°W 128 links



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-13 Found concrete monument with brass cap.

14- Established the Southeast corner of the Northeast quarter of the Southeast quarter of section 35 per B.L.M. instructions for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Found concrete monument with brass cap  
 Wit: 5" Spruce N22°W 7.99'  
 4" Spruce N79°W 8.50'  
 4" Spruce S24°E 16.87'  
 6" Jack pine N47°E 31.55'  
 Concrete Monument Brass cap East 19.16'  
 Carsonite post North 1'

14- Set 5/8" X 32" rod with P.S. cap #33981  
 Wit: Found 1/2" capped iron #12084 S57°E 9.21'  
 3" Balsam N08°W 7.18'  
 28" Red Pine N87°E 35.18'  
 8" White Pine S38°E 35.32'  
 5" White Pine S68°W 26.93'  
 Found 1/2" capped iron #12084 S57°E 9.21'  
 Centerline of N-S Road East 6.5'±  
 Carsonite Post North 1'±

Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 6-14-01