

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 2 E


OSCODA COUNTY

DESCRIPTION OF CORNER 1/4 corner on N. Side Sec. 4, T27N-R2E

CORNER MONUMENT Drove 1"x36" Iron pipe

DATE MONUMENT PLACED AND WITNESSED 5-15-69

WITNESSES TO CORNER.....



7" W. Pine S 64 W 35.2'

3" W. Pine S 62 E 19.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established at midpoint between section corners of Sec. 4. on the standard townline. Corner was set 23.6' east of S $\frac{1}{4}$ Sec. 33, T28N-R2E.

SURVEYOR'S SEAL

SIGNED *Kenneth Dething* DATE 6-9-69
REGISTERED LAND SURVEYOR 10068