

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	12 T. 27 N. 2 R. 2 E. 1/2	M-4; 9
2. PROPERTY CONTROLLING IN SECTION	12 T. 27 N. 2 R. 2 E. 1/2	9
3. MISCELLANEOUS PROPERTY IN SECTION	12 T. 27 N. 2 R. 2 E. 1/2	M-4, 14; 9, 13;
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl R. Johnson, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 28, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

See continued

A. ~~Description of original monument and accessories and/or subsequent restoration:~~

9, 13
Set 5/8" bar w/cap and cedar post
*14" Maple N27°W 8.37'
*12" Maple S 8°W 21.52'

9
Found 1/2" bar w/cap (Caldwell) and post
*8" Maple N40°E 24.00'
*3" Cherry S45°W 22.38'

*Nail and Reference Tag on side of tree

*Nail and Reference Tag on side of tree

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-4 Found county monument in place as set by Norm Caldwell, 1971 survey.
- M-4,14 Set property corner by standard survey procedure for subdivision of sections.
- 9,13 Set property corner by standard survey procedure for subdivision of sections.
- 9 Found corner in place as set by Norm Caldwell, RLS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4
Found county monument
10" Maple S87°W 21.9'
10" Maple S50°E 20.8

M-4, 14
Set 5/8" bar w/cap
*10" Maple N69°W 21.10'
* 4" Maple S56°W 17.70'

*Nail and Reference Tag on side of tree

SIGNED BY *Carl R. Johnson* _____

DATE 4/2/26

SURVEYOR'S MICHIGAN REGISTRATION NO. 30083


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ Oscoda County