

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 5 pg 77

For corners in

Oscoda

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27 N R 2E

T 27N R 1E

T _____ R _____

T _____ R _____

A-2

M-2

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2, T27N, R2E common corner to M-2, T27N, R1E

GLO 1839 Lewis Clason, DS

Mon - Post

Wit: 14" Spr. Pine S51°W 21 lks

8" Spr. Pine N50°W 45 lks

Oct 1995 R. Mitchell, PS

Mon - Set bar & cap in centerline

Wit: Set spike N. side 12" R. Pine N80°E 59.4

Set spike SW. side 8" Oak S44°E 81.78

Set spike SE. side 8" Oak S53°W 40.57

Set spike NE side 13" R. Pine N44°W 74.27

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2, T27N, R2E common corner to M-2, T27N, R1E

Found 1/2"x18" steel rebar with cap #30079/28417 in center of Town line Road. Accepted as a careful and faithful reestablishment of the Government Corner. Replaced with 5/8"x34" Steel Rebar with Oscoda County Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2, T27N, R2E common corner to M-2, T27N, R1E

Mon - Standard Oscoda County Monument

Wit: Found spike N. side 12" R. Pine N80°E 59.4

Nail in S. side 8" J. Pine 8" J. Pine N35°W 45.78

Spike South side 14" Norway S65°E 59.80

Spike North side 9" J. Pine N80°W 34.69

Spike Northeast side 10" J. Pine N25°W 55.75

APPROVED
County Remonumentation
Peer Review Group
NCC
27 JULY 00



Signed by Marvin E. Myers

Date July 10, 2000

Surveyor's Michigan License No. 31600