

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda

(County)

Located In:

Corner Code #

Liber 5 pg 79

1. Public Land Survey

T 27N R 2E
T 27N R 1E
T R
T R

A-4
M-4

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Marvin E. Myers, in a field survey on June 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

1/4 Corner common to Section 12, T27N, R1E and Section 7, T27N, R2E

G.L.O.-1839 Lewis Clason 1968 Consumers Power Co. H.W. Dorcey
Mon.-post Mon - Not given
Wit: 6" Y. Pine S46°W 131 lks Wit: None given
6" Spr. Pine N38°W 164 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/4 Corner common to Section 12, T27N, R1E and Section 7, T27N, R2E

Found "T" iron (typical Consumers Power Company Marker) in Centerline of Town Line Road midway and on line between A-5 and A-3; Accepted "T" iron as a careful and faithful reestablishment of the position of the Government Corner. Replaced "T" iron with 5/8"x34" steel rebar with Standard County Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 Corner common to Section 12, T27N, R1E and Section 7, T27N, R2E

Mon - Standard County Monument.
Wit: Nail N. side 16" Norway N65°W 37.27
Nail N. side 15" Norway N45°W 50.55
Nail S. side 4" J. Pine N90°E 44.21
Nail S. side 4" J. Pine S69°E 46.22

APPROVED

County Remonumentation Peer Review Group

NCC
27 JULY 00



Signed by

[Signature of Marvin E. Myers]

Date July 10, 2000

Surveyor's Michigan License No. 31600

Grid table with columns A-M and rows 1-12. Cell (4,7) contains a dot.